

1 110176

Docket #E-18,039

135 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-20,659 - 0000
NW NW , SEC. 35 , T 32 S, R 41 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3408
Operator: Merrico Resources, Inc.
Name:
Address P.O. Box 849
Ardmore, OK 73402

4620 feet from S section line
4620 feet from E section line
Lease Name Unit Berryman-Richfield Well # 7-3
County Morton 164.12
Well Total Depth 5050 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 800

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 12 p.m. Day: 5 Month: 6 Year: 19 91

Plugging proposal received from Bob Sargent

(company name) Sargent's Casing Pullers (phone) 316-624-7455

were: 5 1/2" at 5048', PBTD 4992', Perfs at 4930-40', Sanded in 1000'

1st plug at free point with 40 sx cement,

2nd plug at 830' with 50 sx cement,

3rd plug at 400' with 30 sx cement,

4th plug at 40-0' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
6-7-91
JUN 07 1991
CONSERVATION DIVISION
Wichita Kansas

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 5 p.m. Day: 5 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1000' with 40 sx cement,

2nd plug at 830' with 50 sx cement,

3rd plug at 450' with 30 sx cement,

4th plug at 40-0' with 10 sx cement.

Remarks: Used common cement by Sargents. Recovered 1040' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-8-91

INV. NO. 32247

Signed James Durrant (TECHNICIAN)