

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22102-00-00  
Spot: W2SWSE Sec/Twnshp/Rge: 24-32S-38W  
660 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: SPIKES B Well Number: 1-24  
County: STEVENS Total Vertical Depth: 6298 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 453 S. WEBB RD. STE 310 PO BOX 78020  
WICHITA, KS 67278

Conductor Pipe: Size feet: 8 3/4  
Surface Casing: Size 8.625 feet: 1468 WITH 425 SX CMT  
Production: Size 4.5 feet: 6298 WITH 200 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/19/2002 11:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: Company: Phone:

Proposed Plugging Method: PUMP BOTTOM 500# HULLS & 25 SX CMT. PLUG AT 1480' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE  
Date/Time Plugging Completed: 12/19/2002 3:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 6252'. PERFS AT 5978-82, 6018-30. PUMP 500# HULLS & 25 SX CMT FOR BOTTOM PLUG. DISPLACE WITH MUD & PRESSURE TO 500 PSIG. SHUT IN. SHOOT OFF CASING AT 1400'. COULD NOT COME LOOSE. SHOT OFF AT 800'. WOULD NOT COME LOOSE. SHOT OFF AT 600'. PULL JOINT. LOAD HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. PULL OUT OF HOLE TO 40'. PUMP 20 SX CMT TO SURFACE.

RECEIVED  
JAN 03 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICE. RECOVERED 600' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland  
(TECHNICIAN)

INVOICED

DATE 1-3-03

INV. NO. 2003061029

Form CP-203