

1100214

TO:

API NUMBER 15-189-21,343-0000

4-6

STATE CORPORATION COMMISSION

NW NW NE NE SEC. 4, T 32 S, R 38 W

CONSERVATION DIVISION - PLUGGING SECTION 200 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1250 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME McCLURE D WELL # 3-H

TECHNICIAN'S PLUGGING REPORT

COUNTY STEVENS 9152

OPERATOR LICENSE # 4549

WELL TOTAL DEPTH 2816 FEET

OPERATOR: ANADARKO PETROLEUM CORP.

PRODUCTION CSG: SIZE 5-1/2" FEET 2815' W/235 SX

NAME AND P.O. BOX 351

SURFACE CSG 8-5/8" FEET 601

ADDRESS LIBERAL KS 67905-0351

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR SARGENTS/HORTON LICENSE NUMBER 31151

ADDRESS RT 1, BOX 49BA TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 6 MONTH: 4 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENTS/HORTON (PHONE) 405-544-7240

WERE: SET CIBP AT 2400' WITH 3 SXS. CEMENT ON TOP. PUMP GEL SPACER TO 1650'

SPOT 50 SX PLUG. GEL TO 650' SPOT 50 SX PLUG HERE. GEL TO 40' 5 SX 40 TO 0'

PLUGGING PROPSAL RECEIVED BY: RICHARD LACY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 12:00PM DAY: 6 MONTH: 4 YEAR: 1998

ACTUAL PLUGGING REPORT CIBP SET AT 2400' WITH 3 SX CEMENT ON TOP. GEL TO 1650. SPOT 50

SX CEMENT PLUG HERE. GEL TO 650'. SPOT 50 SX CEMENT PLUG HERE. GEL

TO 40' SPOT 5 SX PLUG 40' TO SURFACE. PRESSURE UP ON BACKSIDE TO 500

PSI WITH 12 SX CEMENT.

REMARKS: USED 117 SX ELTORO PORTLAND CEMENT BY SARGENTS. NO CASING WAS RECOVERED.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Gary Winters  
(TECHNICIAN) FORM CP-2/3

Rec'd  
RJC  
5-1-98  
5-1-98

**INVOICED**

DATE 5-4-98  
INV. NO. 50418  
4-6