

R

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22328-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 5-32S-38W  
4459 feet from S Section Line, 4029 feet from E Section Line  
Lease/Unit Name: MLP CORNELL UNIVERSITY Well Number: 1  
County: STEVENS Total Vertical Depth: 6270 feet

Operator License No.: 5447  
Operator Name: OXY USA, INC.  
Address: PO BOX 27570  
HOUSTON, TX 77227

10/31

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 1720 WITH 400 SX CMT  
Production: Size 5.5 feet: 6262 WITH 475 SX CMT 203.78  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 10/31/2000 10:00 AM  
Plug Co. License No.: 6547 Plug Co. Name: SARGENTS CASING PULLING SERVICE  
Proposal Rcvd. from: DON HORTON Company: SARGENTS CASING PULLING SER Phone: (316) 697-2500

Proposed Plugging Method: BOTTOM PLUG PUMP 300# HULLS & 25 SX CMT. 1ST PLUG AT 900' WITH 25 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 10/31/2000 2:00 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

DV @ 3097' WITH 200 SX CMT. PERFS AT 5827-5837 & 5856-67'. 1ST PLUG PUMP 3 SX HULLS & 25 SX CMT. 2ND PLUG AT 874' WITH 25 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 0-40' WITH 10 SX CMT. GOOD CIRCULATION THROUGHOUT JOB.

RECEIVED

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 874' OF 5 1/2" CASING.

STATE CORPORATION COMMISSION  
11-2-2000  
NOV 2 2000

Plugged through: CSG

District: 01

Signed

(TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 11/3/00

INV. NO. 2001060931

OCT 31 2000

MP