

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22370-00-00  
Spot: NENESW Sec/Twnshp/Rge: 6-32S-38W  
2114 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: MLP CURTIS B Well Number: 1  
County: STEVENS Total Vertical Depth: 6225 feet

Operator License No.: 5447

Conductor Pipe: Size 13.375 feet: 1114 \$202.51

Op Name: OXY USA, INC.

Surface Casing: Size 8.625 feet: 1835 WITH 515 SX CMT

Address: PO BOX 27570 5 E GREENWAY PLZ STE  
HOUSTON, TX 77227

Production: Size 5.5 feet: 6198 WITH 150 SX CMT

Liner: Size feet:

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/04/2001 1:00 PM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON

Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS WITH 25 SX CMT. 1ST PLUG AT 1860' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/05/2001 11:00 AM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 6154'. PERFS AT 6093-99'. PORT COLLAR @ 3014' WITH 65 SX CMT. PUMPED 200# HULLS WITH 25 SX CMT, PRESSURED TO 800#. 1ST PLUG PULL OUT OF HOLE WITH 5 1/2" TO 1860' & PUMP 50 SX CMT. LOAD HOLE WITH MUD. 2ND PLUG PULL OUT OF HOLE WITH 5 1/2" TO 650' & PUMP 40 SX CMT. LOAD HOLE. 3RD PLUG PULL OUT OF HOLE TO 40' & PUMP 10 SX CMT. CMT TO SURFACE ON 8 5/8" X 13 3/8" ANNULUS.

Remarks: USED COMMON CEMENY BY SARGENTS. RECOVERED 1900' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Jim Holland PART II  
(TECHNICIAN)

RECEIVED

INVOICED

OCT 11 2001

OCT 12 2001

KCC WICHITA

DATE 10-15-01

INV. NO. 2002060801

JP