

TO: 1100337  
STATE CORPORATION COMMISSION

API NUMBER 15-189-22,318-0000  
NE NW SE SEC. 6, T 32 S, R 38 W

CONSERVATION DIVISION - PLUGGING SECTION 2203.3 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1407.7 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MLP CURTIS A WELL # 1

TECHNICIAN'S PLUGGING REPORT 3/15 COUNTY STEVENS 204.75

OPERATOR LICENSE # 5447 WELL TOTAL DEPTH 6300' FEET

OPERATOR: OXY USA INC PRODUCTION CSG: SIZE 5 1/2" @ 6292' WITH 300 SX

NAME AND BOX 2528 SURFACE CASING: SIZE 8 5/8" @ 1492' WITH 425 SX

ADDRESS LIBERAL, KS 67950-2528

ABANDONED OIL WELL        GAS WELL X INPUT WELL        SWD WELL        D/A       

OTHER WELL AS HEREINAFTER INDICATED       

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. LICENSE NUMBER 31151

ADDRESS RT. 1, BOX 49BA TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 13 MONTH: 03 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC. (PHONE) 580-854-6515

WERE: PERFS AT 5879-92. PORT COLLAR AT 3100'.

1ST PLUG SPOT 300# HULLS WITH 25 SX CEMENT TO 5870' AT 900-1000 PSI. 2ND PLUG SPOT 50 SX CEMENT AT 1520'. 3RD PLUG SPOT 50 SX CEMENT AT 550'. 4TH PLUG SPOT 10 SX CEMENT FROM 40'-0'. ON 3/14/00 LOST CIRCULATION ON 550' PLUG. TAGGED CEMENT AT 492'. TOPPED OFF.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL        X        PART        NONE       

OPERATIONS COMPLETED: HOUR: 10:30 AM DAY: 15 MONTH: 03 YEAR: 2000

ACTUAL PLUGGING REPORT       

1ST PLUG SPOT 300# HULLS WITH 25 SX CEMENT TO 5870' AT 900-1000 PSI. 2ND PLUG SPOT 50 SX CEMENT AT 1520'. 3RD PLUG SPOT 50 SX CEMENT AT 550'. 4TH PLUG SPOT 10 SX CEMENT FROM 40'-0'. ON 3/14/00 LOST CIRCULATION ON 550' PLUG. TAGGED CEMENT AT 492'. TOPPED OFF.

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 1930' OF 5 1/2" CASING. RECEIVED STATE CORPORATION COMMISSION  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING. **INVOICED**  
DATE 3/29/00  
SIGNED 06/480

Gary Winters (TECHNICIAN) MAR 27 2000 3-27-2000  
FORM CP-213 CONSERVATION DIVISION  
Wichita, Kansas