

1091036

TO: STATE CORPORATION COMMISSION

API NUMBER 15-129-21,599 - 0000
C SE SW SE SEC. 5, T 32 S, R 40 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HALL WELL # 1-155

TECHNICIAN'S PLUGGING REPORT 1/27 COUNTY MORTON 182.00

OPERATOR LICENSE # 32468 WELL TOTAL DEPTH 5600 FEET

OPERATOR: PIONEER OIL COMPANY PRODUCTION CSG: SIZE " FEET

NAME AND RR 4 BOX 142B SURFACE CASING: SIZE 8 5/8" @ 1600' WITH SX

ADDRESS LAWRENCEVILLE, IL 62439

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR BIG A DRILLING LICENSE NUMBER 31572

ADDRESS P.O. BOX 1856 LIBERAL, KS 67905-1856

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 27 MONTH: 01 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM GEORGE PAYNE

(COMPANY NAME) BIG A DRILLING (PHONE) 316-624-1904

WERE:

1ST PLUG AT 3100' WITH 100 SX CEMENT. 2ND PLUG AT 1630' WITH 50 SX CEMENT.

3RD PLUG AT 500' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

 PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 2:30 PM DAY: 27 MONTH: 01 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 3100' WITH 100 SX CEMENT. 2ND PLUG AT 1630' WITH 50 SX CEMENT.

3RD PLUG AT 500' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY HALLIBURTON.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM?)

I DID NOT OBSERVE THIS PLUGGING 2/8/00 SIGNED [Signature]

DATE 06/23/00

(TECHNICIAN)

FORM CP-2/3

FEB - 8 2000

2-8-2000
CONSERVATION DIVISION

[Signature]