


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 35 Twp. 19S Rge. ~~XX~~ 19(W)
Location as "NE/CNW/SE" or footage from lines C SW SW
Lease Owner Beardmore Drilling Company, et al
Lease Name Wagner Unit Well No. 1
Office Address 700 - 120 Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 7-19 19 67
Application for plugging filed 7-19 19 67
Application for plugging approved 7-19 19 67
Plugging commenced 7-19 19 67
Plugging completed 7-19-67 19 67
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5108 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay and shells		0	195			
Shale and shells		195	340			
Shale and shells		340	437			
Anhydrite		437	445	8-5/8"	445'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

0 to 40' - 10 sacks cement

40' - wood plug

40' to 285' - heavy mud

285' to 360' - 25 sacks cement

360' - wood plug

360' to 5108' - heavy mud

also - 2 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Gabbert-Jones, Inc.
Address: 830 Sutton Place, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Heber Beardmore (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Heber Beardmore*

(Address)

SUBSCRIBED AND SWORN to before me this 24th day of July, 19 67

My commission expires 7-13-71

Shirley Ann Jackson
Shirley Ann Jackson Notary Public.



GABBERT JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

WAGNER UNIT #1
C SW SW SECTION 35-29S-19W
KIOWA COUNTY, KANSAS

COMMENCED: JULY 5, 1967
COMPLETED: JULY 19, 1967

OPERATOR - BEARDMORE DRILLING CO.

DEPTH	FORMATION	REMARKS
From	To	
0	195	CLAY AND SHALE
195	340	SHALE, SHELLS AND RED BED
340	437	SHALE AND SHELLS
437	445	ANHYDRITE
445	455	ANHYDRITE
455	695	RED BED AND SHALE
695	1630	SHALE AND SHELLS
1630	2615	SHALE AND LIME
2615	2925	LIME
2925	4545	LIME AND SHALE
4545	4615	LIME
4615	4642	LIME AND SHALE
4642	4970	LIME
4970	5041	LIME AND SHALE
5041	5108	LIME
5108	TD	DRY AND ABANDONED.

RAN 22 JOINTS OF 8-5/8" CASING, SET @ 445' w/250 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1967
CONSERVATION DIVISION
Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C SW SW SECTION 35-29S-19W, KIOWA COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 21ST DAY OF JULY, 1967, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1968.

