

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Schmidt
 WELL NUMBER C 2

660 Ft. from S Section Line
3300 Ft. from E Section Line
 SEC. 35 TWP. 29 RGE. 19 ~~(N)~~ or (W)

COUNTY KIOWA
 Date Well Completed 12-30-85
 Plugging Commenced 11-26-99
 Plugging Completed 11-30-99

LEASE OPERATOR VINCENT oil corp.
 ADDRESS 125 N. MARKET #1075
 PHONE (316) 262-3573 OPERATORS LICENSE NO. 5004
 Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)
 The plugging proposal was approved on 11-26-99 (date)
 by Dodge KCC (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? Not Available

Producing Formation MISS Depth to Top 5047 Bottom 5056 T.D. 5182
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 3/8	650	
				4 1/2	5182	2030


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set:
Sanded to 4997' BAILED 4 SKS SHOT 2030' PULLED TO 1150' PUMPED
10 GEL + HOLE WITH 50 SKS PULLED TO 650' PUMPED 50 SKS PULLED TO 40'
PUMPED 10 SKS PULLED LAST JOINT HOLE STAYED FULL

Name of Plugging Contractor DWS License No. 31925
 Address 249 BETH DR STERLING K.S. 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: VINCENT oil corp.
 STATE OF K.S. COUNTY OF SEWICK, ss.

Richard A. Hiebsch (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Richard A. Hiebsch, Pres.
 (Address) Same as above



SUBSCRIBED AND SWORN TO before me this 8th day of December, 1999
Yolanda Eubanks KANSAS CORPORATION COMMISSION
 Notary Public

My Commission Expires: 10-9-2001 DEC 09 1999
12-9-99 Form CP-4 Revised 05-88
 CONSERVATION DIVISION
 WICHITA, KS

ALLIED CEMENTING CO., INC.

2195

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Medicine Lodge

DATE <u>11-30-99</u>	SEC. <u>35</u>	TWP. <u>29S</u>	RANGE <u>19W</u>	CALLED OUT <u>12:00 pm</u>	ON LOCATION <u>1:20 pm</u>	JOB START <u>1:50 pm</u>	JOB FINISH <u>3:15 pm</u>
LEASE <u>SCHMIDT</u>	WELL# <u>C-2</u>	LOCATION <u>Coldwater N to Parkin</u>			COUNTY <u>Kiowa</u>	STATE <u>KS.</u>	
OLD OR NEW (Circle one)		<u>Ranch sign - 1/4 1 1/2 W 1/4 S</u>					

CONTRACTOR Quality Well Service
 TYPE OF JOB OTF
 HOLE SIZE _____ T.D. _____
 CASING SIZE 4 1/2 DEPTH 1250'
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX 100 MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER Vincent
 CEMENT
 AMOUNT ORDERED 110 5x 60:40:6
10 5x 66
5 5x Hulls
 COMMON A 66 @ 6.35 419.10
 POZMIX 44 @ 3.25 143.00
 GEL 16 @ 9.50 152.00
 CHLORIDE _____ @ _____
C.S. Hulls 500# @ 15.50 77.50
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 HANDLING 110 @ 1.05 115.50
 MILEAGE 110 x 42 @ .04 184.80
 TOTAL \$1091.90

EQUIPMENT

PUMP TRUCK CEMENTER Carl Baldwin
 #261-265 HELPER Shane Winsor
 BULK TRUCK
 #214-314 DRIVER Kevin Brungard
 BULK TRUCK
 # _____ DRIVER _____

REMARKS:

1st plug 1250'
Load Hole w/ 10 5x 66L + 5 5x Hulls.
Pump 50 5x 60:40:6 - 1250'
50 5x - 680'
10 5x - 40'

SERVICE

DEPTH OF JOB 1250'
 PUMP TRUCK CHARGE _____ 450.00
 EXTRA FOOTAGE _____ @ _____
 MILEAGE 42 @ 2.85 119.70
 PLUG _____ @ _____
 _____ @ _____
 _____ @ _____
 TOTAL \$569.70

CHARGE TO: Vincent Corp
 STREET 125 N. MARKET, ST. 1075
 CITY WECHITA STATE KANSAS ZIP 67302

FLOAT EQUIPMENT

_____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX 106.34
 TOTAL CHARGE 1767.94
 DISCOUNT 332.32 IF PAID IN 30 DAYS
1435.62
Richard O. McAtypke
 PRINTED NAME

SIGNATURE Richard O. McAtypke