


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat.

Kiowa County. Sec. 36 Twp. 29 Rge. 19 (E) W (W)
Location as "NE/CNW&SW" or footage from lines C SE SW
Lease Owner Mull Drilling Co. Inc.
Lease Name Windle Well No. 1
Office Address 670 N. 4th. Natl. Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-2 1961
Application for plugging filed 1-2 1961
Application for plugging approved 1-2 1961
Plugging commenced 10:00 A. M. 1-2 1961
Plugging completed 1:00 P. M. 1-2 1961
Reason for abandonment of well or producing formation No production.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5107 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole was filled with drilling mud to within 240 ft. of top of hole. Plug was put at this depth with 1/4 sack hulls on top of plug and 20 sacks cement put on top of hulls through drill pipe. Hole then filled to within 40 ft. of top and a plug put at this depth, 1/4 sack hulls put on top of plug. Ten sacks cement then put on top of plug, this filled hole to top. Two sacks cement was then pu in rat hole bridging same. This completed plugging.

RECEIVED
STATE CORPORATION COMMISSION
1-10-61 JAN 10 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Co. Tools.
Address Same as above.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Joseph O. Butts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph O. Butts
Mull Drilling Co. - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of January, 19 61

My commission expires January 28, 1961

Ethel Zimmerman
Ethel Zimmerman Notary Public.

ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Inc. Et Al
Wichita, Kansas

ROTARY DRILLING COMMENCED: 12/14/60

CONTRACTOR: Mull Drilling Co., Inc.
Wichita, Kansas

ROTARY DRILLING COMPLETED: 1/2/61

CASING RECORD: Set 8 5/8" @ 550' w/350 sx cmt.
D & A

LOCATION: WINDLE #1
C SE SW 36-29S-19W
Kiowa County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing.)

645'	Red Bed	
1250'	Shale, etc.	
2150'	Shale w/Lime	
2220'	Lime w/Shale	
2440'	Lime	
2569'	Lime w/Shale	
3100'	Lime	
3327'	Lime & Shale	
3520'	C.Lime & Shale	
3725'	Lime w/Shale	
3951'	Sandy Lime w/Shale	
4522'	Lime w/Shale	
4559'	Lime	
4645'	Lime w/Shale	
4733'	Lime	
4848'	Lime	
4993'	Lime w/Shale	
5044'	Lime	
5087'	Lime w/Shale	
5107'	Mississippi	total depth

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1961
CONSERVATION DIVISION
Wichita, Kansas


I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

R. James Gear
R. James Gear

STATE OF KANSAS)
) SS
) SEDGWICK

Subscribed and sworn to before me this 6th day of January, 1961.



Walter H. Miller
Notary Public

My Commission Expires: 2/24/62