

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-097-20690-0000

API NUMBER _____
LEASE NAME Coolidge #1
WELL NUMBER _____
SPOT LOCATION C NW NW
SEC. 27 TWP. 29 RGE. 19W(E) or (W)
COUNTY Kiowa
Date Well Completed 11/30/80
Plugging Commenced 3/6/85
Plugging Completed 3/12/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR D.R. Lauck Oil Co., Inc.

ADDRESS 221 S. Broadway, Suite 400, Wichita, Ks. 67202

PHONE # (316) 263-8267 OPERATORS LICENSE NO. 5427

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 5209'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	659'	none
				4 1/2"	5204'	3277'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged bottom with sand to 5070' & 4 sacks cement. Shot pipe at 4700', 4000', 3500' and 3277'. Pulled 91 joints of pipe. Plugged well with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug, & 170 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1985

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION
Wichita, Kansas

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 18th day of March, 1985



Irene Hoover
Notary Public

My Commission expires: _____

D. R. Lauck Oil Company, Inc. - Coolidge #1
 221 S. Broadway, Suite 400 C NW NW Sec. 27-29S-19W
 Wichita, Kansas 67202 Kiowa County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
 221 S. Broadway, Suite 400
 Wichita, Kansas 67202

Commenced: October 20, 1980
 Completed: October 30, 1980

Drillers Log

Clay, Sand & Shale	662
Shale & Shells	1520
Shale	2520
Shale & Lime	2735
Shale	2935
Shale & Lime	3540
Lime & Shale	3730
Shale & Lime	4135
Lime & Shale	4735
Lime	4967
Lime & Shale	5017
Lime	5190
Lime & Shale	5210 RTD

Casing: 659' 8-5/8" cemented with 400 sacks Common Cement,
 2% Gel, 3% Calcium Chloride.
 5204' 4-1/2" cemented with 125 sacks 60-40 Pozmix
 Salt Saturated Cement, 8% Gilsonite.

RECEIVED
 STATE CORPORATION COMMISSION

JAN 15 1985

CONSERVATION DIVISION
 Wichita, Kansas