

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kiowa SEC. 28 TWP. 29S RGE. 19W E/W
Location as in quarters or footage from lines:
330' FNL & 1320' FWL NW/4

Lease Owner Wells Energy Corporation
Lease Name Butler Well No. 1
Office Address 700 S. Colorado Blvd.-Suite 454, Denver, CO 80222
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed September 11, 1981
Application for plugging filed Verbal application
Plugging commenced September 11, 1981
Plugging completed September 11, 1981
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice V. Leslie

Producing formation _____ Depth to top _____ bottom T.D. 5,209'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	669'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

- 900' - 60 sxs
- 650' - 50 sxs
- 40' - 10 sxs + 1/2 sk hulls + SWBP
- RH - 5 sxs
- MH - 5 sxs

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1981

9-21-81

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Dowell Div., Dow Chemical Co.
Santa Fe and Hwy. 281, Pratt, KS CONSERVATION DIVISION
67124 Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Gary Younger, Agent (~~owner~~ of owner) or (~~owner~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
251 N. Water, #10, Wichita, Ks.
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 17th day of September, 19 81

Helen Pracht
Helen Pracht - Notary Public.

My Commission expires: June 4, 1985

KANSAS DRILLERS LOG

COMPANY Wells Energy Corporation

SEC. 28 T. 29S R. 19W
Loc. 330' FNL & 1320' FWL NW/4

FARM Butler NO. 1

COUNTY Kiowa

ROTARY TOTAL DEPTH 5,209'
COMM. August 31, 1981 COMP. September 11, 1981
CONTRACTOR H-30, INC. (Rig #77)
ISSUED September 17, 1981

CASING

10 3/4"
8 5/8" Set at 669' cemented w/575 sxs cement
5 1/2"
4 1/2"


ELEVATION 2,387' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed	1,740'
Red Bed and Anhydrite	2,090'
Lime and Shale	2,250'
Shale and Shells	2,482'
Shale	2,683'
Lime and Shale	3,465'
Shale and Lime	3,658'
Lime and Shale	4,045'
Shale and Lime	4,103'
Lime and Shale	4,460'
Sand and Lime	4,539'
Lime and Shale	5,055'
Chat and Chert	5,159'
Chert	5,209'
Rotary Total Depth	5,209'

I hereby certify the above and foregoing to be
a true and correct log of the above described
well as shown by the drilling reports.

H-30, INC.



Gary Younger

State of Kansas)
) ss:
County of Sedgwick)

Subscribed and Sworn to before me a Notary Public
in and for said county and state this 17th day of
September, 1981.



Helen Pracht - Notary Public

My Commission Expires:

June 4, 1985

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1981
CONSERVATION DIVISION
Wichita, Kansas