

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER. 15-097-20,589-0000

LEASE NAME Edmonston

WELL NUMBER "D" #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1320 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 22 TWP 29 RGE. 19 (E) or (W)

COUNTY Kiowa

LEASE OPERATOR Pickrell Drilling Co., Inc.

ADDRESS Box 1303, Great Bend, Kansas 67530

PHONE # 816-793-5742 OPERATORS LICENSE NO. 5123

Date Well Completed _____

Character of Well oil

Plugging Commenced 3-27-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-5-89

Did you notify the KCC District Office prior to plugging this well? Yes

Which agent did you notify? Steve Pfeiffer and Richard Lacey

Is AGO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom 5199'

Show depth and thickness of all water, oil and gas formations.

T.D. RECEIVED
4-7-89
STATE CORPORATION COMMISSION
APR 7 1989

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	664'	None
				4-1/2"	5185'	3,530.10'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 5050' and 4 sacks cement. Shot casing at 4500', 4000' and 3500'. Pull 45 joints of 4-1/2" casing. Allied plugged well with 400# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug and pumped 130 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 600 psi and shutin 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 6th day of April, 19 89

My Commission Expires: _____
Notary Public Iona M. Leatherman
Barton County, Kansas
My Appt. Exp. 7-26-91