

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County, Sec. 22 Twp 29S Rge. 19W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
NW NW NW


Lease Owner D. R. Lauck Oil Co.
Lease Name Miller #1-H Well No. _____
Office Address Ellinwood, Kansas 67526
Character of Well (Completed as Oil, Gas or Dry Hole) _____

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 8/10/78 _____ 19____
Plugging completed 8/17/78 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation _____ Depth to top, _____ Bottom _____ Total Depth of Well 5150
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8 | 622 | none |
| | | | | 4 1/2" | 5147 | 3493' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Squeezed 4 1/2" casing with 50 sacks cement, pumped plug to 4400'. Shot pipe at 4320', spotted
45 bbls. Pumped plug to 4200', 4025', 3480', pulled 105 joints. Squeed hole with
3 sacks hulls, 25 sacks gel, released plug and displaced 150 sacks 50/50 pozmix,
2% gel, 3% cc.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of August, 19 78

My commission expires _____

MARGARET MELCHER
Rice County, Ks.
My Comm. Exp. Feb. 15, 1979

Margaret Melcher
STATE CORPORATION Notary Public.

AUG 23 1978

CONSERVATION DIVISION
Wichita, Kansas

D. R. Lauck Oil Company, Inc. - Miller "H" #1
 NW NW NW Sec. 22-29S-19W
 Kiowa County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
 301 S. Broadway
 Wichita, Kansas 67202

Commenced: May 10, 1976
 Completed: May 26, 1976

Drillers Log

| | |
|--------------|----------|
| Clay & Shale | 200 |
| Shale & Sand | 580 |
| Sand | 615 |
| Shale | 625 |
| Shale & Sand | 1075 |
| Shale | 1275 |
| Anhydrite | 1296 |
| Shale | 2130 |
| Shale & Lime | 2873 |
| Lime | 5150 RTD |

RECEIVED
 STATE CONSERVATION COMMISSION

JUL 27 1978

CONSERVATION DIVISION
 Wichita, Kansas