

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-097-20,542-0001

LEASE NAME EAGLE CANYON RANCH

WELL NUMBER 1

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 30 TWP. 29 RGE. 19W (E) or (W)

COUNTY KIOWA

Date Well Completed 7/84

Plugging Commenced 3/22/93

Plugging Completed 3/24/93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR J. MARK RICHARDSON

ADDRESS 155 N. MARKET #840 WICHITA, KS. 67202

PHONE#(316) 262-3192 OPERATORS LICENSE NO. 5414

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/19/93 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? YES

Producing Formation MISSISSIPPI Depth to Top 5080 Bottom 5092 T.D. 5145

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
MISSISSIPPI	GAS	0	559	8 5/8	559	0
		0	5145	4 1/2	5145	3551

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. sand back to 5040 dump bail 4 sk cement cut and pull 3551' of 4 1/2 casing

pump 300# hulls - 10 sk gel-50 cement - 10 gal - 100# hulls - 8 5/8 plug - 150 sk cement  
all cement 60/40 poz 6% gel mix 500#, ISIP 100# 15 sk cement down water well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor GREENSBURG WELL SERVICE License No. 5414


Address 303 E. KANSAS, GREENSBURG, KS. 67054

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: J. MARK RICHARDSON

STATE OF SEDGWICK COUNTY OF KANSAS, ss.

J. MARK RICHARDSON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
Address 155 N. MARKET #840 WICHITA, KS. 67202



RECEIVED  
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 9TH day of JUNE, 19 93

6-10-93

CONSERVATION DIVISION

My Commission Expires Wichita, Kansas 6-22-96

[Signature]  
Notary Public