

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117
NOV 27 1985

API NUMBER 15-097-20,815-0000

LEASE NAME Rose

WELL NUMBER 1-21

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 21 TWP. 29S RGE. 19W (E) or (W)

COUNTY Kiowa

Date Well Completed 11/18/81

Plugging Commenced 10-31-85

Plugging Completed 11-1-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Graham-Michaelis

ADDRESS P. O. Box 247, Wichita, Kansas 67201
~~Box 769, 769th Street, Oklahoma, 73801~~

PHONE# (405) 256-6491 OPERATORS LICENSE NO. 5134

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City Paul Luthi

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 5112 Bottom 5165' T.D. 5212 (5165PB)

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	627	none
				4 1/2	5209	4014

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 25 sks. of cement & 1 sk. of hulls from 5122 to 4900

Pump 40 sks. of cement from 1300 to 1200

Pump 50 sks. of cement from 660 to 560

Put 10 sks. of cement from 40 to 0 Cut off & cap 8 5/8 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506 Liberal, Kansas 67901

STATE OF Kansas COUNTY OF Seward Sedgwick, ss.

Jack L. Yinger, Vice President (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack L. Yinger


(Address) Graham-Michaelis Corporation
P. O. Box 247, Wichita, KS 67201

SUBSCRIBED AND SWORN TO before me this 5th day of December, 19 85

Aldine M. Johnson
Notary Public

STATE CORPORATION COMMISSION

My Commission Expires:



DEC 6 1985

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84