


15-097-10145-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

KIOWA County. Sec. 23 Twp. 29 Rge. 19 (NW) (W)
Location as "NE/CNW/SW" or footage from lines APPROXIMATELY C-E/2
Lease Owner PETROLEUM, INC.
Lease Name NEWBY Well No. 1
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed JUNE 6 19 57
Application for plugging filed JULY 10 19 57
Application for plugging approved JULY 12 19 57
Plugging commenced JULY 20 19 57
Plugging completed JULY 29 19 57
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well M. A. RIVES PRATT, KANSAS
Producing formation Depth to top Bottom Total Depth of Well 5077 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	663'	NONE
MISSISSIPPI	WATER AND LITTLE GAS	5062'	5066'	5 1/2"	5075'	4100'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

(PLUGGED BACK TO 5073.5')

FILLED HOLE WITH CRUSHED ROCK FROM 5073.5' TO 5050' AND PLACED 5 SACKS CEMENT ON TOP OF ROCK. MUDDED UP TO 350' AND PLACED SOLID ROCK BRIDGE ON TOP OF MUD. PLACED 20 SACKS CEMENT ON TOP OF ROCK BRIDGE AND MUDDED UP TO 30'. MADE SOLID ROCK BRIDGE AT 30' AND FILLED HOLE TO BASE OF WELL CELLAR WITH 10 SACKS CEMENT.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor MORGAN WELL PLUGGING SERVICE
Address 102 WEST 18TH STREET, HUTCHINSON, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
R. D. BREW (employee of owner) or (Notary Public) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
ROUTE 2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 31ST day of JULY, 19 57

My commission expires JULY 11, 1960

[Signature]
RECEIVED Notary Public
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 23 T. 29 R. 19W
BOOK PAGE 26 LINE 40

8-1-57 AUG 1 1957
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

15-097-10145-0000

COMPANY PETROLEUM, INCORPORATED

SEC. 23 T. 29S R. 19W

FARM NEWBY

NO. 1


LOC. C/E/2

TOTAL DEPTH 5077'

COUNTY Kiowa Co., Kansas

COMM. February 26, 1957 COMP. March 13, 1957

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 663' W/450 sax.
5 1/2" @ 5075' W/100 sax.

ELEVATION 1341' DF

PRODUCTION Mississippian

FIGURES INDICATE BOTTOM OF FORMATIONS

10	Surface soil
130	Clay
200	Sand
350	Sand & shale
360	Shale
475	Clay
665	Shale & gyp
1775	Red bed & shale
1990	Salt & shells
2455	Shale & shells
2615	Lime & shale
2802	Lime
2937	Lime & shale
3145	Lime
4110	Lime & shale
4964	Lime
5010	Cherty lime
5045	Lime & shale
5052	Lime
5077	Cherty lime.
5077	T. D.

State of KANSAS

County of BARTON

I, Verne A. Morris

of

Garvey Drilling Co.

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Newby well

Subscribed and sworn to before me this 2nd day of May 19 57

My Commission Expires: July 11, 1960

Notary Signature
NOTARY PUBLIC

RECEIVED
STATE CORPORATION COMMISSION

AUG 1 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 23 T 29 R 19W
BOOK PAGE 36 LINE 40