

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERRY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-189-20784-00-00

LEASE NAME H.H. Wulfmeyer

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

WELL NUMBER 1

SPOT LOCATION SE-NE

LEASE OPERATOR Belco Energy Corporation

SEC. 11 TWP. 32S RGE. 35 (E) OR (W) (W)

ADDRESS 8908 S Yale Suite 340 Tulsa, OK 74137-3522

COUNTY Stevens

PHONE # (918) 481-6020 OPERATORS LICENSE NO. 31269

DATE WELL COMPLETED 5-25-85

CHARACTER OF WELL OIL  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMMENCED 6-29-01

PLUGGING COMPLETED 7-3-01

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? DODGE CITY

IS ACO-1 FILED? YES IF NOT, IS WELL LOG ATTACHED? YES

PRODUCING-FORMATION MORROW DEPTH TO TOP \_\_\_\_\_ BOTTOM T.D. 6450

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>MORROW</u>	<u>OIL, GAS, WATER</u>	<u>6070</u>	<u>6076</u>	<u>9 5/8</u>	<u>1875</u>	<u>-0-</u>
				<u>5 1/2</u>	<u>6448</u>	<u>2010</u>
				<u>2 7/8</u>	<u>6123</u>	<u>6123</u>

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Pump and circulation method used. Circulate wellbore with 110 bbl mud. Set CIBP at 6020 with 2 sx cement on top. Cut casing off at 2010' Pumped 75 sx cement from 1900' to 1750' Pull pipe up to 550'. Pumped 50 sx cement 550' to 450'. Pulled pipe to 40'. Pumped 15 sx cement from 40' to surface. Cut off and welded steel ID plate 4' BGL

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)


NAME OF PLUGGING CONTRACTOR JERRY DUNKIN WELL SERVICES INC LICENSE NO. 8733  
ADDRESS P.O. Box 389 Enid Oklahoma 73702

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, SS.

PAUL DAVIS

(EMPLOYEE OF OPERATOR) OR

(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.



(SIGNATURE) Paul Davis  
(ADDRESS) 8908 S YALE STE 340 TULSA OK 74137

SUBSCRIBED AND SWORN TO BEFORE ME THIS 16 DAY OF AUGUST, 2001

Terry J Frohnappell  
NOTARY PUBLIC

MY COMMISSION EXPIRES: 1-23-05

RECEIVED

AUG 20 2001  
8-20-01  
KCC WICHITA

FORM CP-4  
REVISED 06-83

OR