

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-189-21,363-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR McCoy Petroleum Corporation OPERATORS LICENSE NO. 5003

ADDRESS 110 S. Main, Suite 500 PHONE # (316) 265-9697

LEASE (FARM) Fern Sessler WELL NO. 2-21 WELL LOCATION NE NW SE COUNTY Stevens

SEC. 21 TWP. 32S RGE. 35 or TOTAL DEPTH 6470' PLUG BACK TO _____

Check One:

OIL WELL _____ GAS WELL _____ D & A SWD OR INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 1784' CEMENTED WITH 600 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Plug using Halliburton 60-40 Pozmix,

6% gel. Set 1st plug @ 3200' w/100 sacks, 2nd plug @ 1810' w/50 sacks, 3rd plug @ 800'

w/40 sacks, 4th plug @ 40' w/10 sacks. 15 sacks in ratehole and 10 sacks in mousehole.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACC-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 7:00 a.m. 8-1-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Eugene Saloga PHONE # (316) 256-3510

ADDRESS Garden City, Kansas

PLUGGING CONTRACTOR Sweetman Drilling Company LICENSE NO. 5658

ADDRESS 110 S. Main, Suite 500, Wichita, Kansas PHONE # (316) 265-5561

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Eugene Saloga
(Operator or Agent)

DATE: 8-1-89

RECEIVED
STATE CORPORATION COMMISSION
AUG 7 1989
CONSERVATION DIVISION
Wichita, Kansas

8-7-89