

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

RECEIVED
STATE CORPORATION COMMISSION
SEP 6 1989
CONSERVATION DIVISION
Wichita, Kansas

9-6-89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-189-21,347-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR McCoy Petroleum Corporation OPERATOR'S LICENSE NO. 5003 *e/ro*

ADDRESS 110 S. Main, Suite 500; Wichita, KS 67202 PHONE # (316) 165-9697

LEASE (FARM) Wulfemeyer "A" WELL NO. 1-2 WELL LOCATION C NW SW COUNTY Stevens

SEC. 2 TWP. 32S RGE. 35 or TOTAL DEPTH 6349 PLUG BACK TD 6288

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 1758 CEMENTED WITH 625 SACKS

CASING SIZE 4-1/2" SET AT 6344 CEMENTED WITH 200 SACKS

PERFORATED AT 6077-6087

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP in 4-1/2" casing @ 6000'. Place 3 sx of cement on top of CIBP. Cut off and pull 4-1/2" casing. Plug hole with Pump truck using 60-40 Pozmix, 6% gel, as follows: Botton of 1st plug @ 3150' w/50 sx, bottom of 2nd plug @ 2600' w/50 sx.

(If additional space is needed use back of form.) (See Back)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 8:00 a.m. 9-8-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE # (316) 532-5292

ADDRESS Kingman, Kansas

PLUGGING CONTRACTOR J.W. Gibson Well Service LICENSE NO. 5866 *e/ro*

ADDRESS P. O. Box 1510, Liberal, Kansas PHONE # (316) 626-5303

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: *Daryl Hanson*
(Operator or Agent)

DATE: 9-6-89

①

Bottom of 3rd plug @ 1780' w/40 sx., Bottom of 4th plug @ 600' w/40 sx.,
Bottom of top plug @ 40' w/10sx. Plug rathole with 15 sacks.
Plug mousehole with 10 sacks.



Kansas Corporation Commission

MIKE HAYDEN
 KEITH R. HENLEY
 RICH KOWALEWSKI
 MARGALEE WRIGHT
 JUDITH McCONNELL
 FRANK A. CARO, JR.

GOVERNOR
 CHAIRMAN
 COMMISSIONER
 COMMISSIONER
 EXECUTIVE DIRECTOR
 GENERAL COUNSEL

CONSERVATION DIVISION
 SHARI FEIST ALBRECHT, DIRECTOR
 200 Colorado Derby Bldg.
 202 W. 1st Street
 Wichita, KS 67202-1286
 (316) 263-3238

September 7, 1989
**NOTICE OF RECEIPT OF
 WELL PLUGGING APPLICATION**

McCoy Petroleum Corporation
 110 S. Main, Suite 500
 Wichita, KS 67202

Wulfemeyer "A" 1-2
 C NW SW
 02-32-35W
 Stevens County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
 Shari Feist Albrecht
 Director

District: #1 304 W. McArtor

Dodge City, KS 67801

(316) 225-6760
