

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-21353-0000

LEASE NAME MLP Gillespie A

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to
Cons. Div. Office within
30 days.

1980 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 3 TWP. 32S RGE. 39 (X) or (W)

COUNTY Stevens

Date Well Completed 8/22/89

Plugging Commenced 6/24/94

Plugging Completed 6/27/94

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100

PHONE# (405) 749-2309 Operators License #5447

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/18/94 (date)

by _____ (KCC District Agent's name).

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation Mor S-4 Depth to Top 5810 Bottom 5850 T.D. 6270

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled Out |
|----------------|------------|-------------|-------------|--------------|-------------|------------|
| <u>Mor S-4</u> | <u>Gas</u> | <u>5810</u> | <u>5850</u> | <u>8 5/8</u> | <u>1716</u> | |
| | | | | <u>5 1/2</u> | <u>6256</u> | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Set CIBP @ 5750. 2sx cmt on top of plug. RIH w/ tbq to 5700', Circ w/ 8.5ppg drlq mud. Laid down tbq to 2900. Pumped 75sx Portland cmt, 1.18 cu ft/sx & 15.6 ppg. Spotted plug from 2900-2255. Laid down tbq to 1800. Spotted plug #3 from 1800-1550. 30sx Portland cmt mixed @ 1.18 cu ft/sx & 15.6 ppg. Laid down tbq to 700. (See back side of form)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J W Gibson Co. License No. 5866

Address 117 N Hwy 27, P. O. Drawer K, Elkhart, Ks 67950

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry Ledlow

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 14th day of July 1994

Sammy L. Padilla
Notary Public

My Commission Expires: 8-21-96 7-18-94

Form CP-4
Revised 05-88

Spotted plug #4 from 700 to 440. 30sx Portland cmt mixed @ 1.18 cu ft/sx & 15.6 ppg. Laid down tbg to 64. Circ 10sx to surface. Laid down last 2 jnts. Filled to surface w/ 1sx cmt. Cut off csg 4' below surface and welded cap. Cleaned up location.