

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-221550000

LEASE NAME VANSELOUS "A"

WELL NUMBER 6

4950 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 2 TWP. 32 RGE 39 (E) or (W)

COUNTY STEVENS

Date Well Completed 9-26-97

Plugging Commenced 12-8-97

Plugging Completed 12-8-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-7-97 (date)

by MR. GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. 6230

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1699	NONE
				5-1/2"	6217	2133

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. MIRU CP. PMP 3 SXS HULLS & 25 SXS CMT PLUG FROM 5608-5808'. PULL FREE POINT ON 5/8" CSG & SHOT OFF @ 2133'. TOH W/ 5/8" CSG TO 1730'. PMP 50 SXS CMT FROM 1580 TO 1730'. TOH TO 650'. PMP 40 SXS CMT 550 TO 650'. TOH TO 40'. PMP 10 SXS CMT FROM 0-40'. TOH W/ REMAINING 5-1/2" CSG. CUT OFF AND CAP 8-5/8" CSG 4' BELOW GL. PERMANENTLY INSCRIBE WELL NAME AND NUMBER AND DATE PLUGGED ON CAP. KCC REP. GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49A, TYRONE, OKLAHOMA 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

JAN 21 1998
1-21-98
CONSUMER PROTECTION DIVISION
Wichita, Kansas

(Signature) L. Marc Harvey

(Address) L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT
P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 19th day of January 1998

Freda L. King
Notary Public

My Commission Expires:

