

15-189-00305-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finley State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA (SPUD 04/23/66)
LEASE NAME VANSELOUS "A"
WELL NUMBER 2
1250' Ft. from S Section Line
1250' Ft. from E Section Line
SEC. 02 TWP. 32S RGE 39 (E) or (W)
COUNTY STEVENS
Date Well Completed 05/04/66
Plugging Commenced 08/28/97
Plugging Completed 09/03/97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION
ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351
PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549
Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 08/20/97 (date)
by MR. GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation COUNCIL GROVE Depth to Top 2712' Bottom 2820' T.D. 2930'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
COUNCIL GROVE	GAS	2712	2820	8-5/8"	597	4'
				5-1/2"	2928'	1601'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. MIRU PU. ROH W/RODS & BHP. TOH W/TBG. RDMO PU. MIRU SARGENTS PMP 3 SXS HULLS & 25 SXS CLASS H CMT. DISPLACE TO 2612 W/9 PPG MUD. PULL FREEPOINT & SHOOT OFF 5-1/2" CSG @ 1601'. CIRC HOLE FULL OF 9 PPG MUD. PMP 40 SXS CMT FROM 1600-1500. TOH W/52 JTS 5-1/2" CSG. PMP 10 SXS CLASS H CMT FROM 40-4'. CUT OFF & CAP 8-5/8" CSG 4' BELOW GL. INSCRIBE CAP. RESTORE LOCATION. NOTIFIED KCC REP GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman
JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 24th day of September, 1997.

Shirley J. Childers
Notary Public

RECEIVED
KANSAS CORP COM
MY 01 SEP 25 P 12:05
9-25-97

Commission Expires: _____

