

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189-20116 - 0000

LEASE NAME Gustason

WELL NUMBER 2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1320 Ft. from S Section Line

1323 Ft. from E Section Line

SEC. 29 TWP. 32S RGE. 38W (E) or (W)

COUNTY Stevens

LEASE OPERATOR Mobil Oil Corporation

ADDRESS 2319 North Kansas, Liberal, KS 67901

PHONE# (316) 626-1160 OPERATORS LICENSE NO. 5208

Date Well Completed 3/1972

Character of Well Gas

Plugging Commenced 1/8/92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1/10/92

The plugging proposal was approved on 1/9/92 (date)

by Glen Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? -----

Producing Formation Council Grove Depth to Top 2840 Bottom 2988 T.D. 3040

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Council Grove	Gas	0	600'	8 5/8"	600'	0
		0	3039'	5 1/2"	3039'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

See Attached

RECEIVED

STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form. JAN 22 1992)

Name of Plugging Contractor Halliburton License 1-22-92

Address Liberal, KS CONSERVATION DIVISION  
Wichita, Kansas


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mobil Oil Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Rae Kelly, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Kelly

(Address) Mobil Oil Corporation  
2319 N. Kansas, Liberal, KS 67901



SUBSCRIBED AND SWORN TO before me this 20th day of January, 19 92

Sharon A. Cook  
Notary Public

10-1-94

\*\*\*\*\*

MSD95\$

\*\*\* PRISM \*\*\*

Page 1

01/08/1992

DAILY COMPLETION OR WORKOVER SUMMARY REPORT

16:00

Lease: GUSTASON  
Field:  
API #: 15-189-20116-00  
Contractor: PATRICK WELL  
AFE Number:  
Supt: B. WRIGHT  
Budget Category:

Well #: 002  
State: KS  
Ppty ID: 2424500  
Rig: RIG 8  
AFE Amount: M  
Engineer: E. PARKS

Well ID: 0002620  
County: STEVENS  
OOS #:  
Water Depth:  
Mobil GVI: 100.000%

Report Start Date: 01/08/1992  
Report End Date: 01/08/1992  
Depth:  
TV Depth:  
Daily Cost: 2 M

Starting Time: 12:00  
Time Ended: 16:00  
Max. Hole Angle:  
FBTD:  
Cumm Cost: 2 M

Job Type: WORKOVER  
Reference Height:  
Accident Reported? N  
Violation Reported? N  
Plan Cost: M

===== DAILY SUMMARY =====

PLUG AND ABANDON WELL

===== CURRENT STATUS =====

SET CIBP, 2 SX OMT

===== WORK PLANNED FOR NEXT PERIOD =====

OMT

===== OPERATIONS SUMMARY =====

MOVED IN AND RIG UP PATRICK WELL SERVICE. ROSEL ON LOC. RAN IN W/CIBP AND SET AT 2820' KB. RAN IN AND PLACE TO SX OF OMT ON PLUG W/BAILER. SION

===== PERSONNEL =====

Name Title

T ROMERO SUPERVISOR

Report Generated On: 01/16/92 @ 02:59 End of Report.....

\*\*\*\*\*

RECEIVED  
STATE CORPORATION COMMISSION

JAN 22 1992

CONSERVATION DIVISION  
Wichita, Kansas

Lease: GUSTASON Well #: 002 Well ID: 0002620  
 Field: State: KS County: STEVENS  
 API #: 15-169-20116-00 Ppty ID: 2424500 OOS #:  
 Contractor: PATRICK WELL Rig: XRIG 8 Water Depth:  
 AFE Number: AFE Amount: M Mobil GVI: 100.000%  
 Supt: B. WRIGHT Engineer: E. PARKS  
 Budget Category:

Report Start Date: 01/09/1992 Starting Time: 07:00 Job Type: WORKOVER  
 Report End Date: 01/09/1992 Time Ended: 13:30 Reference Height:  
 Depth: Max. Hole Angle: Accident Reported? N  
 TV Depth: FBTD: Violation Reported? N  
 Daily Cost: 3 M Cumm Cost: 5 M Plan Cost: M

===== DAILY SUMMARY =====

OMT WELL

===== CURRENT STATUS =====

OMT WELL IN

===== WORK PLANNED FOR NEXT PERIOD =====

OUT AND OAP

===== OPERATIONS SUMMARY =====

RAN IN 89 JT OF 2 3/8 TBG, LANDED AT 2800'+-. HALLIBURTON ON LOCATION. HOOKED UP TO TBG STRING AND CIRCULATED 65 BBLS OF 36 VIS 9# GEL. PULLED 35 JTS., 54 STILL IN HOLE 1700'+-. HOOKED BACK UP TO TBG., BALANCE IN 10 SX OMT OVER ANHYDRITE. PULLED 32 JTS., 22 JTS STILL LEFT IN HOLE 689+-. 89' BELOW SURFACE. HOOKED UP TO ANNULUS (8 5/8 - 5 1/2) PUMPED IN 7 BBLS OMT, BACKSIDE OMT TO SURFACE. HOOKED UP TO TBG., CIRCULATED OMT TO SURFACE 16 BBLS. POOH W/TBG STRING. WELL OMT IN, TOTAL OMT USED 75 SX 60/40 FOZMIX. WITNESSED BY KOO GLEN BARLOW.

===== PERSONNEL =====

Name	Title
T ROMERO	SUPERVISOR

Report Generated On: 01/16/92 @ 02:59 End of Report.....  
 \*\*\*\*\*

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 22 1992  
 CONSERVATION DIVISION  
 Wichita, Kansas

\*\*\*\*\*

MSD956

\*\*\* PRISM \*\*\*

Page 1

01/10/1992

DAILY COMPLETION OR WORKOVER SUMMARY REPORT

10:00

Lease: GUSTASON  
Field:  
API #: 15-189-20116-00  
Contractor: PATRICK WELL  
AFE Number:  
Supt: B. WRIGHT  
Budget Category:

Well #: 002  
State: KS  
Ppty ID: 2424500  
Rig: RIG 8  
AFE Amount: M  
Engineer: E. PARKS

Well ID: 0002620  
County: STEVENS  
OOS #:  
Water Depth:  
Mobil GWI: 100.000%

Report Start Date: 01/10/1992  
Report End Date: 01/10/1992  
Depth:  
TV Depth:  
Daily Cost: 0 M

Starting Time: 08:00  
Time Ended: 10:00  
Max. Hole Angle:  
PBD:  
Cumm Cost: 5 M

Job Type: WORKOVER  
Reference Height:  
Accident Reported? N  
Violation Reported? N  
Plan Cost: M

===== DAILY SUMMARY =====

OUT OFF AND CAP WELL

===== CURRENT STATUS =====

WELL PLUGGED AND ABANDONED

===== WORK PLANNED FOR NEXT PERIOD =====

FINAL REPORT

===== OPERATIONS SUMMARY =====

F & O ROUSTABOUT SERVICE DUG OUT AROUND WELL HEAD. WILLIAMS WELDING OUT OFF SURFACE AND PRODUCTION STRING AND CAPPED. OUT OFF APPROX., 5-6' BELOW GL.

===== PERSONNEL =====

Name

Title

I ROMERO

SUPERVISOR

Report Generated On: 01/16/92 @ 02:59

End of Report.....

\*\*\*\*\*

RECEIVED  
STATE CORPORATION COMMISSION

JAN 22 1992

CONSERVATION DIVISION  
Wichita, Kansas

COUNCIL GROVE FIELD

# GUSTASON #1-2

S29-32S-38W SE 1/4

STEVENS COUNTY, KANSAS

DATUM LEVEL IS K.B. 11' ABOVE G.L.

Well cut off & capped 5-6' below G.L. KB ELEV: 11'


CURRENT WELLBORE

Pumped in 7 bbls Cmt down annulus - loaded

Circulated to surface 16 bbls Cmt

12 - 600' Cement 350 SX CIRC.

12 - 600' 8 5/8" OD 24#/11 J 55 Casing



609

36 vis 9# Goll

12 - 3039' Cement 415 SX CIRC.

1600

35 bbls Cmt

1700

36 vis 9# Goll

RECEIVED STATE CORPORATION COMMISSION

JAN 22 1956

CONSERVATION DIVISION Wichita, Kansas

2SK Cmt on Plug C1BPC 2820

2840 - 2988' Perts 2 SPF

12 - 3039' 5 1/2" OD 14#/11 J 55 Casing  
3032 - 3040' 7 7/8" OD Openhole  
3012 - 3040' Cement Plug PBTD

PBTD: 3012'

Mobil - PRISM