

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finley State Office Building
 130 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-189-21281 - 0000

LEASE NAME BEESLEY "D"

WELL NUMBER 1H

1390 Ft. from S Section Line

4030 Ft. from E Section Line

SEC. 13 TWP. 32S RGE 38 (E) or (W)

COUNTY STEVENS

Date Well Completed 12/22/88

Plugging Commenced 2/21/97

Plugging Completed 3/04/97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/14/97 (date)

by GARY WINTERS (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 2560' Bottom 2864' T.D. 2920'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHASE	GAS	2560'	2864'	8-5/8"	604'	3'
				5-1/2"	2918'	3'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. MIRU WL. SET CIBP @ 2350'. DMP 2 SXS CMT ON TOP. LD HOLE W/2575 GAL 9 PPG MUD & PRESS TST TO 1000# - HELD. RIH & PERF CMT SQZ HOLES @ 630'-631'. PMPD 70 BBL DM - UNABLE TO CIRC. PMP 145 SXS CLASS H CMT - UNABLE TO CIRC. RIH W/SLICK LINES & TAG TOC @ 151'. MIRU WL & PERF 149'-150' W/4SPE. CIRC 2PPG MUD DWN CSG & UP ANNULUS. PMPD 60 SXS CLASS H CMT & CIRC TO SURFACE CUT OFF & CAP 8-5/8" CSG & 5-1/2" CSG 3' BELOW GL & INSCRIBED CAP. KCC WITNESS: GARY WINTERS

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HALLIBURTON ENERGY SERVICES License No. 5287

Address P.O. BOX 1598, LIBERAL, KS 67905-1598 PHONE: (316) 624-3879

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman


JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 6th day of March, 1997.

Tammy Cranford
 Notary Public

My Commission Expires: 3/22/2000



RECEIVED
 STATE CORP. COMM
 3-7-97