

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 1518910010 - 0001

LEASE NAME MCCLURE

WELL NUMBER A2-16

4620 1980 Ft. from S Section Line

4620 1980 Ft. from E Section Line

SEC. 16 TWP. 32S RGE. 38 (E) or (W)

COUNTY STEVENS

Date Well Completed _____

Plugging Commenced 6-19-2002

Plugging Completed 6-20-2002

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-10-2002 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation GLORIETTA Depth to Top 1500 Bottom 1600 T.D. 3047 ⁶⁰⁸⁵ Pb Td 7000

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
GLORIETTA	SWD	1500	1600	13 3/8	586	0
				8 5/8	3047	0

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. CIRCULATE 9 PPG MUD. DUMP 2 SXS 13 3/8 ANNULUS. PLUG 8 5/8 W/ 50 SXS CMT FROM 1260-1110. TAG AT 1170. PLUG 600-500 WITH 30 SXS CMT. LOAD HOLE WITH MUD. PLUG 75 TO SURFACE WITH 40 SXS CMT. CUT OFF AND CAP 13 3/8 AND 8 5/8 CSG 3' BELOW GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.

CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters

CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101



Subscribed and sworn to before me this 3 day of September, 2002

Lori Pearson
Notary Public

My Commission Expires: 2/26/05

CR