

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finney State Office Building
 30 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-189-19001-0000
~~45-139-21250~~

LEASE NAME HEINTZ

WELL NUMBER 1-8

3960 Ft. from S Section Line

4980 Ft. from E Section Line

SEC. 8 TWP. 32S RGE. 37 (E) or (W)

COUNTY STEVENS

Date Well Completed 3-3-47

Plugging Commenced 3-10-98

Plugging Completed 3-10-98

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

1998 MAY -6 12:22

5-6-98

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on JAN 21, 1998 (date)

by GARY WINTERS (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 2481 Bottom 2740 T.D. 2740

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHASE	GAS	2481	2740	10-3/4	678	0
				7	2552	0
				5-1/2	101	0

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
MIRU. PUMP 80 BBL SW TO KILL WELL. 1D RODS & TBG. SET CIBP @ 2530. DMP 5 SXS CMT ON CIBP. PUMP 40 SXS CMT FROM 550-750'. PUMP 10 SXS CMT TO PLUG FROM 50 TO 3'. CUT OFF AND CAP CSG 3' BELOW GL. STATE WITNESS : STEVE MIDDLETON.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON Plugging, INC. License No. 31151

Address RT.1, BOX 498A TYRONE, OK 73951-9731 PHONE: (580) 845-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shawn D. Young
 SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 4th day of May, 1998.

Shirley J. Childers
 Notary Public

My Commission Expires: _____

