

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-189-20121-00-00

LEASE NAME Moorehead Unit 1

WELL NUMBER 2

1320 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 8 TWP. 32 RGE. 37 (S or W)

COUNTY Stevens

Date Well Completed 07-72

Plugging Commenced 4-9-03

Plugging Completed 4-10-03

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR ExxonMobil Oil Corporation

ADDRESS PO Box 4358 Houston TX 77210

PHONE (713) 431-1828 OPERATORS LICENSE NO. 5208

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-9-03 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation COUNCIL GROVE Depth to Top 2923 Bottom 3005 T.O. 3055

Show depth and thickness of all water, oil and gas formations.

5-12-03

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>8 5/8</u>	<u>600</u>	<u>-</u>
				<u>5 1/2</u>	<u>3054</u>	<u>900</u>

RECEIVED
STATE CORPORATION COMMISSION
MAY 12 2003
WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each so
2 3/4 was sanded in hole. Top of junk @ 1215 5 1/2 was stuck @ 900. Cut & TOH w/ 5 1/2 Ran 2 3/4 to 900 Circ. hole w/ mud & mixed 30 SX cmt. 900 to 800 50 SX 630 to 480 10 SX 40 to 0 Cut off & capped 8 3/4 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: EXXON MOBIL

STATE OF KANSAS COUNTY OF STEVENS, ss.

RICHARD B. LEWIS (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) RBLewis

(Address) PO Box 400 HUGOTON KS 67951

NOTARY PUBLIC, State of Kansas
JANET K. LEWIS
My Appt. Exp. 7-25-06

SUBSCRIBED AND SWORN TO before me this 6th day of MAY, 2003

Janet K Lewis
Notary Public

My Commission Expires: 7-25-06