

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 Finney State Office Building  
 30 South Market, Rm 2078  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-189-00244 - 0000

LEASE NAME HOLT

WELL NUMBER 1-17

3960 Ft. from S Section Line

2744 Ft. from E Section Line

SEC. 17 TWP. 32S RGE 37 ( E ) or ( W )

COUNTY STEVENS

Date Well Completed 2-25-47

Plugging Commenced 12-7-97

Plugging Completed 12-7-97

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-24-97 (date)

by GARY WINTERS (KCC District Agent's Name)

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation CHASE Depth to Top 2570 Bottom 2820 T.D. 2820

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Formation	Content	From	To
CHASE	GAS	2570	2820

CASING RECORD

Size	Put In	Pulled Out
10-3/4"	606	4'
7"	2544	4'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. MIRU CP. SET CIBP @ 2500. DMP 2 SXS CMT ON CIBP. PMPD 40 SXS CMT @ 1700 - 1500. PMP 40 SXS CMT @ 630-430. PMP 10 SXS CMT @ 50 - 0'. CUT OFF 7' CSG 4' BELOW GI & CAP. WITNESSED BY STATE REP GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT 1, BOX 498A, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.  
SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shawn D. Young  
 SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 27th day of January, 1998

Shirley J. Childers  
 Notary Public

My Commission Expires: \_\_\_\_\_

