

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-189-10177-0001

API NUMBER 15-189-220350000 <sup>NA</sup>

LEASE NAME Moorhead Unit

WELL NUMBER 1

1320 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 17 TWP. 32 RGE. 37 (E) or (W)

COUNTY Stevens

Date Well Completed 8-19-42

Plugging Commenced 1-8-96

Plugging Completed 1-9-96

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Mobil Oil Corporation

ADDRESS P. O. Box 2173, Liberal, KS

PHONE#(316) 626-1160 OPERATORS LICENSE NO. 5208

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-4-96 (date)

by Steve Phifer (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Chase Depth to Top 2593 Bottom 2795 T.D. 2850

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Chase	Gas	0	611	12-1/2	611	0
		0	2405		2405	0
		2368	2612	7" liner	244	0
		2612	2848	5" liner	236	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set

SEE ATTACHED

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Patrick Well Service License No. KANSAS CORPORATION COMMISSION

Address 200 W. 7th Street, Liberal, KS 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mobil Oil Corporation

STATE OF Kansas COUNTY OF Seward, ss.


R. Kelly

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) R. Kelly

(Address) Mobil Oil Corporation

P. O. Box 2173, Liberal, KS



SUBSCRIBED AND SWORN TO before me this 18<sup>th</sup> day of January, 19 96

Kathleen R. Poulton

Notary Public

My Commission Expires: August 18 1998

MOOREHEAD 1

SE 1/4 17-32-37  
STEVENS COUNTY

PLUG & ABANDONMENT OF WELL

PATICK WELL SERVICE

NOTE: THIS WELL HAS BEEN PLUGGED AND A REPLACEMENT WELL DRILLED.

1/6/96 MOVED RIG GO LOCATION.

1/8/96 RIG UP. DS ON LOCATION, RIG UP TO WELL HEAD, KILLED WELL, WITH 140 BBLs OF LEASE H<sub>2</sub>O, BROKE WELL HEAD DOWN TO 8 5/8 COLLAR, REMOVING MASTER VALVE. INSTALLED CMT HEAD. PUMPED IN 50 BBLs OF MUD (9# 36 VIS), CONTAINING 500# COTTON SEED HALS. FLOWED W/46 SX THIX CMT, 8 5/8 WIPER PLUG, 4SX CMT. DISPLACED PLUG TO TOP OF LINER, W/113 BBLs OF MUD & 44 BBLs OF H<sub>2</sub>O. UPON SHUTTING DOWN, WELL STILL TAKING FLUID ON VACUUM. (APPARENTLY HOTER CMT DIDN'T STOP CMT FROM DROPPING AROUND PLUG AND GOING INTO PERFS., ALONG W/MOST OF MUD). RAN IN W/2 3/8 TBG AND TAGGED PLUG AT 2368' GL. PUMPED DOWN TBG., STRING AND SPOTTED 50 SX 60/40 POZ MIX ON PLUG. PULLED 10 JTS. SION

1/9/96 NLS WIRELINE ON LOCATION. RAN DOWN & TAGGED CMT PLUG AT 2338'. (THIS GIVES US 30' OF CMT ON TOP OF PLUG ON 7" LINER, AND CMT'D INSIDED OF 9" CSN). RAN TBG DOWN TO 2315+-. DS HOOK UP TO TBG. CIRCULATED TO SURFACE 9#, 36 VIS GEL. PULLED TBG UP TO 1752, BALANCED IN A 50 SX PLUG (60/40 POZ MIX) OVER ANHYDRATE ZONE (THIS SHOULD BE APPROX. A 200' PLUG). PULLED TBG. OUT OF HOLE. ROSEL PERFORATORS ON LOCATION. RAN IN W/4" CSN GUN, 4SPF., PERF., 9" AT 668'. HOOKED UP TO WELL, PUMPED FRESH H<sub>2</sub>O & ESTABLISHED CIRCULATION TO PIT. MIX & PUMP 415 SX (60/40 POS MIX), CIRCULATED TO SURFACE, HAD GOOD CMT RETURNS. WELL PLUGGED.

1/11/96 F&O, DUG DOWN AROUND WELL HEAD, RED WELDING, CUT OFF SURFACE & PRODUCTION STRING, 5' BELOW GROUND LEVEL. WELDED ON CAP. WELL OFFICALLY P&A'D.

WITNESS BY KANSAS COMMISSION: GARY WINTER  
WENT OVER PROCEEDURE W/KCC: STEVE PHIFER

FINAL REPORT

TOM ROMERO, PRODUCTION TECH.

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 19 1996

CONSERVATION DIVISION  
WICHITA, KS

50 SHEETS EYEGLASS 5 SQUARE  
100 SHEETS EYEGLASS 5 SQUARE  
200 SHEETS EYEGLASS 5 SQUARE  
RECYCLED WHITE 5 SQUARE  
MADE IN U.S.A.



Dig around  
Surface & cut  
Cut off & cap 5' below GL

514 ST  
60/40 Poz M. 1/4  
C.C. →

Top of Cmt 200'

Surface  
12 1/2 Cmt w/50%  
Production 9" 2405 - 75SX  
Ports 2593-2795

2611  
668 Port 4 spt

34 Hds  
Gel  
9# 36 is →

50 ST 60/40 Poz M. 1/4  
155Z Anky rate 200' Plug  
175Z

39 Hds  
Gel  
9# 36 U.S. →

50 ST 60/40 Poz M. 1/4 w/30%  
30" of Cmt on top 2338

2368  
Top of liner 2368  
2405 Top Refs 2553

Ramped 50 ST  
7" liner

Ramped 50 Hds  
mud w/50%  
huls  
5 1/2" liner

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 19 1996

CONSERVATION DIVISION  
WICHITA, KS