

15-129-00197-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-129-95004 (of this well) 6/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Amoco Production Company OPERATORS LICENSE NO. 5952

ADDRESS P. O. Box 432 Liberal, KS 67905-0432 PHONE # (316) 624-6241

LEASE (FARM) Renshaw G.U. A WELL NO. 1 WELL LOCATION SW NE COUNTY Morton

SEC. 21 TWP. 32S RGE. 39 (R) or (W) TOTAL DEPTH 2662 PLUG BACK TD None

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 10-3/4 SET AT 605 CEMENTED WITH 400 SACKS

CASING SIZE 5-1/2 SET AT 2623 CEMENTED WITH 300 SACKS

PERFORATED AT 2453-86; 2523-70 2592-2616

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK Casing Collapsed _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL See back of form

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Already filed IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN December 15, 1987

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: 12-3-87

Bob Heath PHONE # (316) 624-6241

ADDRESS P. O. Box 432 Liberal, KS 67905-0432

RECEIVED
STATE CORPORATION COMMISSION
DEC 3 1987
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING CONTRACTOR To be bid LICENSE NO. _____

ADDRESS _____ PHONE # () _____

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Larry L. Smith
(Operator or Agent)

DATE: 11-30-87

①



Amoco Production Company

November 17, 1987

File: LRP-533-400.1

PxA Procedure
Renshaw G.U. "A" No. 1
Section 21-T32S-R39W
Morton County, Kansas

Detailed below is the PxA procedure for the subject well. A wellbore sketch showing the collapsed casing and the hole in the casing is attached.

1. Set a CIBP at 1280'. Cap with two sacks of cement.
2. Fill hole from cement cap to 630' with 9 ppg mud.
3. Spot 50 sacks of cement. This should give a 100' plug.
4. Fill hole from cement plug to 33' with 9 ppg mud.
5. Spot 20 sacks of cement from 33' to 3'.
6. Cut off casing 4' below ground level. Weld on steel cap and inscribe proper identification.

C. H. Kelm

RSW/sac

Attachment

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

THIS NOTICE

MAR 07 '88

EXPIRES

December 7, 1987

WELL PLUGGING NOTICE

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

Renshaw G.U. A #1
SW NE
Sec. 21-32S-39W
Morton County

Amoco Production Company
P. O. Box 432
Liberal, KS 67905


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,



Shari Feist
Director
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760