

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-129-10136-0000 (of this well) 6/87  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Amoco Production Company OPERATORS LICENSE NO. 5952

ADDRESS P. O. Box 432 PHONE # (316) 624-6241

LEASE (FARM) Tillet G. U. "B" WELL NO. 1 WELL LOCATION SWNE COUNTY Morton

SEC. 19 TWP. 32S RGE. 39  or  (W) TOTAL DEPTH 6050 PLUG BACK TD 5868

Check One:

OIL WELL \_\_\_\_\_ GAS WELL X D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8 SET AT 710 CEMENTED WITH 500 SACKS

CASING SIZE 4 1/2 SET AT 5906 CEMENTED WITH 450 SACKS

PERFORATED AT 5724-26; 5816-18; 5830-32

CONDITION OF WELL: GOOD X POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL See attached form

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN November 7, 1986

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bob Heath PHONE # (316) 624-6241

ADDRESS P. O. Box 432, Liberal, Kansas 67901

PLUGGING CONTRACTOR To be bid LICENSE NO. 11-4-86

ADDRESS \_\_\_\_\_ PHONE # ( ) NOV 4 1986

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Larry L. Smith  
(Operator or Agent)

DATE: 11-3-86

①

State of Kansas



JOHN CARLIN  
MICHAEL LENNEN  
MARGALEE WRIGHT  
KEITH R. HENLEY  
JUDITH A. McCONNELL  
BRIAN J. MOLINE

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary  
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
200 Colorado Derby Building  
202 West 1st Street  
WICHITA, KANSAS 67202-1288

THIS NOTICE

FEB 4 '87

EXPIRES

November 4, 1986

WELL PLUGGING NOTICE

Tillet G. U. "B" #1  
SW NE  
Sec. 19-32S-39W  
Morton County

Amoco Production Company  
P. O. Box 432  
Liberal, KS 67901

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely, ..

A handwritten signature in black ink, appearing to be "J. McCord", written over a horizontal line.

Jack McCord, Director

Please contact the district office to review your suggested method of plugging  
DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760  
five days prior to plugging the well (KAR-82-3-113).



Amoco Production Company

P. O. Box 432  
Liberal, KS 67901

October 28, 1986

File: RAR-717-400.1

Plugging and Abandonment Procedure  
Tillett G. U. "B" No. 1  
Section 19-32S-39W  
Morton County, Kansas

Detailed below is the recommended plugging and abandonment procedure for the subject well. Depths are relative to the Induction-Electrical log run by Schlumberger on February 20, 1961. Note that this procedure is for KCC permitting purposes only.

1. MIRUSU or casing pullers, unset packer and pull 2 3/8" tubing and packer.
2. Run a gauge ring and CIBP, set CIBP at 5680', cap with 2 sacks cement (NOTE: Wellbore has DV tool at 3125').
3. Locate free point of 4 1/2" casing (see attached wellbore sketch), cut off and pull casing. Estimated top of cement is 2300'.
4. Spot a 50 sack 50-50 Poz cement plug across the 4 1/2" casing stub.
5. Spot a 75 sack cement plug across the 8 5/8" surface casing shoe (50' in and out of casing shoe), shoe set at 710'.
6. Spot a 50 sack cement plug from 40-5'.
7. Dig out cellar, cut off surface casing at 5'. Weld on steel cap with well and location I.D.
8. Restore location.

NOTE: All intervals between cement plugs must contain mud of at least 9.0 ppg density, and 36 quart-second API viscosity. A representative of the KCC must be notified at least five days prior to the actual plugging operation to discuss plugging methods. They (KCC) can be contacted at (316)225-6760.

A wellbore sketch is attached for your reference.

C. H. Kelm

BSP/sac

Attachment

NOV 4 1986