

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89  
RECEIVED  
STATE CORPORATION COMMISSION  
5-3-91  
MAY 03 1991

WELL PLUGGING APPLICATION FORM  
(File One Copy)

CONSERVATION DIVISION  
Wichita, Kansas

API NUMBER 15-189-20,473-0000 (of this well).  
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Anadarko Petroleum Corporation OPERATOR'S LICENSE NO. 4549 8/91

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) Hickok "B" WELL NO. 1 WELL LOCATION 1980' FN & EL COUNTY Stevens

SEC. 13 TWP. 32S RGE. 39 (E) or (W) TOTAL DEPTH 6012 PLUG BACK TD 5716

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8 SET AT 1637 CEMENTED WITH 800 SACKS

CASING SIZE 4 1/2 SET AT 6012 CEMENTED WITH 200 SACKS

DV Tool @ 3142. Cemented w/700 sxs  
PERFORATED AT 5755-5763' CIBP set @ 5716'

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Spot 2 sxs cmt on CIBP. Spot 50 sxs cmt across 1670-1570',  
30 sxs cmt 850-750' and 10 sxs from 40-3'. Cut off csg 3' below surface.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon Approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE  
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

O. J. Stuck PHONE # (316) 544-7240

ADDRESS P.O. Box 208, Hugoton, Kansas 67951-0208

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547 9/91

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: J. L. Ashton  
(Operator or Agent) J. L. Ashton  
Division Production Mgr

DATE: May 2, 1991

①



WIRELINE SERVICES  
GEARHART-OWEN

DUAL INDUCTION-LAT

FILING NO.	COMPANY ANADARKO PRODUCTION COMPANY		
	WELL HICKOK "B" NO. 1		
	FIELD YOUNGGREN		
	COUNTY STEVENS	STATE	KANSAS
	LOCATION: RECEIVED STATE CORPORATION COMMISSION SW NE		
	SEC 13	TWP CONSERVATION DIVISION Wichita, Kansas	RGE 39W
	Permanent Datum G.L.	Elev.	3120
	Log Measured from G.L.	-0-	Ft. Above Perm. Datum
	Drilling Measured from G.L.		

*Exhibit "F"*

MAY 03 1991

Date	9-16-79			
Run No.	One			
Depth-Driller	6012			
Depth-Logger	6014			
Bottom Logged Interval	6013			
Top Logged Interval	1632			
Casing-Driller	8 5/8 @ 1633	@	@	
Casing-Logger	1632			
Bit Size	7 7/8			
Type Fluid in Hole	Chem. Gel			
Density and Viscosity	9.4 80			
pH and Fluid Loss	9.0 9.8 cc		cc	cc
Source of Sample	Flowline			
Rm @ Meas. Temp.	2.0 @ 68 °F	@	°F	@ °F
Rmf @ Meas. Temp.	1.4 @ 68 °F	0.766 @ 130 °F	0.847 @ 117 °F	°F
Rmc @ Meas. Temp.	3.0 @ 68 °F	@ 5 °F	@ °F	°F
Source of Rmf and Rmc	M M			
Rm @ BHT	1.05 @ 130 °F	@	°F	@ °F
Time	End Circulation	0700		
	Logger on Bottom	1130		
Max Rec. Temp. Deg	130 °F		°F	°F
Equip. No. and Location	7553 Liberal			
Recorded By	Temple			

Joan Finney  
Governor

Jim Robinson  
Chairman

Keith R. Henley  
Commissioner

Rachel C. Lipman  
Commissioner

Judith McConnell  
Executive Director

Brian J. Moline  
General Counsel



# Kansas Corporation Commission

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

May 3, 1991

Anadarko Petroleum Corporation  
P. O. 351  
Liberal, KS 67905-0351

Hickok B 1  
API 15-189-20,473-  
1980'FNL-1980'FEL  
Sec. 13-32-39W  
Stevens County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor

District: #1 304 W. McArtor  
Dodge City, KS 67202  
(316) 263-8809

Conservation Division  
William R. Bryson  
Director  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202-1286  
Telephone (316) 263-3238