

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

15-189-00305-0000

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # NA 4/23/66 (SPUD) (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549 <sup>8/97</sup>  
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE (316) 624-6253

LEASE VANSELOUS "A" WELL# 2 SEC. 2 T. 32S R. 39 (XXXX/West)

NW - NW - SE - SE SPOT LOCATION/QQQQ COUNTY STEVENS

1250 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

1250 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#                     

CONDUCTOR CASING SIZE                      SET AT                      CEMENTED WITH                      SACKS

SURFACE CASING SIZE 8-5/8" SET AT 597' CEMENTED WITH 400 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 2928' CEMENTED WITH 200 SACKS

2712-16, 2723-26, 2729-31, 2736-41, 2750-57

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: 2766-71, 2775-76, 2781-83, 2792-98, 2814-20

ELEVATION 3221' / -- T.D. 2930' PBD 2922' ANHYDRITE DEPTH 1702'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING PMP 35 SXS CMT + 2 SXS HULLS DISPLACE TO 2662' W/9PPG MUD. PULL FREE PT & SHOOT OFF 5-1/2" CSG. CIRC HOLE FULL W/9PPG MUD. SPOT 25 SXS CMT @ CUT-OFF DEPTH. PULL CSG TO 647'. SPOT 45 SXS CMT FROM 647'-547'. PULL CSG TO 54'. SPOT 17 SXS CMT FROM 54'-4'. CUT OFF & CAP 8-5/8" CSG 4' BELOW GL. RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MR. DAVE GILMORE PHONE# (316) 544-7240

ADDRESS P.O. BOX 208 City/State HUGOTON, KANSAS 67951 <sup>1/98</sup>

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151  
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 7/14/97 AUTHORIZED OPERATOR/AGENT: John A. Broman

JOHN A. BROMAN (signature) DIV. PROD. ENGR.

RECEIVED  
KANSAS CORP COM  
JUL 21 1997

7-21-97

**ANADARKO PETROLEUM CORPORATION**

PHONE 316 - 624 - 6253    1701 NORTH KANSAS AVE.    P.O. BOX 351    LIBERAL, KANSAS 67905 - 0351



July 17, 1997

Kansas Corporation Commission  
Conservation Division  
Finney State Office Building  
130 South Market, Rm. 2078  
Wichita, Kansas 67202

Attn.: Marguerite Fox

Re: Plugging Record (Form CP-4)

Vanselous "A" No. 2  
Sec 02-32S-39W  
Stevens County, Kansas

Howell-Rhinehart No. 2  
Sec. 23-32S-39W  
Stevens County, Kansas

Hayward "J" No. 1  
Sec. 29-34S-39W  
Morton County, Kansas

Dear Ms. Fox:

Enclosed in duplicate is a Well Plugging Record (KCC Form CP-4) for the referenced well. Please file accordingly.

If additional information is required, please contact this office at the letterhead address.

Very truly yours,

John A. Broman  
Division Production Engineer  
AMC/sjc

Enclosures

cc: TRC - HGO  
Manager Land Administration - HGO  
WI Owners  
Well File

kccplug1.doc

KANSAS RECEIVED  
1997 JUL 21 P 1:29  
KANSAS CORP COMM



## Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner  
Judith McConnell, Executive Director David J. Heinemann, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

July 22, 1997

Anadarko Petroleum Corporation  
P O Box 351  
Liberal KS 67905-0351

Vanselous "A" #2  
API 15-N/A  
1250 FSL 1250 FEL  
Sec. 02-32S-39W  
Stevens County

Dear Mr. Dave Gilmore,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760