

LEASE NAME Quigg "A"

WELL NUMBER #1-33

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 33 TWP. 32S RGE. 38 or W

COUNTY Stevens

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 3017 N. Cypress, Wichita, KS 67226

PHONE# (316) 636-2737 OPERATORS LICENSE NO. 5003

Character of Well Gas

Date Well Completed 2-1-95

Plugging Commenced 4-11-95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-11-95

The plugging proposal was approved on Glenn Barlow April 11, 1995 (date)

by _____ (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Lower Morrow Sand Depth to Top _____ Bottom _____ T.D. 6200'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	1448	8-5/8"	1448'	None
		0	6119	4-1/2"	6119'	1408'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
See Attached

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
RECEIVED
MAY 15 1995
CONSULTATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor J. W. Gibson Well Service License No. 5-5866

Address 7400 E. Orchard Rd. #370, Englewood CO 80111-2531


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF KANSAS, ss.

McCoy Petroleum Corporation, (Employee of Operator) or Operator of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) _____

(Address) 3017 N. Cypress
Wichita, KS 67226-4003



Subscribed and sworn to before me this 3rd day of May, 1995
Deborah Ann Paulus
Notary Public
January 8, 1996

J. W. GIBSON WELL SERVICE COMPANY

HWY 54 EAST • P.O. BOX 1383 • GUYMON, OK 73942
TELEPHONE (405) 338-0664

P&A DEPARTMENT

4/11/95 P&A PROCEDURE


McCOY PETROLEUM CORP.	1-33 Quigg "A"
Sec 33, T32S, R38W	C S/2 S/2 SW
Stevens Co., Kansas	API #15-189-21,791

8 5/8 24# 1448'	4 1/2" 10.5# 6199'
DV 3129.81 250sx. TOC 1500'	(200sx. TOC 5300')
Perfs. 6082-88 Plugged CIBP 6072'	PBTD 6072'
Perfs. 6034-42	

JOB LOG:

MIRU JWG R79 and plugging equipment.
 Fill Hole w/mud. 96bbls.
 ELI RIH set CIBP 5950+- dump 2 sx. cem. on top.
 Work stretch on csg. TOC 1500', surface 1448'.
 Cut csg. at freepoint. 1408'+-
 Mix and spot 50 sx. cem. at 1408'. TOC 1243'
 POOH to 712'+- (Per KCC recomendations, Glenn Barlow).
 Mix and spot 40 sx. cem. TOC 580'
 POOH
 Mix and circulate 10 sx. cem. 34' to surface.
 RDMO
 Dig out, cut off, cap, and refill.
 Job complete.
 Witnessed by Glenn Barlow with KCC.

TOM PATTEN
 ASSISTANT P&A MGR.



cc: Glenn Barlow KCC
 Darrel Hanson, McCoy Petroleum Corp.

RECEIVED
 STATE CORPORATION COMMISSION

MAY 15 1995

CONSERVATION DIVISION
 WICHITA, KANSAS