

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-189-21281-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549 8/97  
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE (316) 624-6253

LEASE BEESLEY "D" WELL# 1H SEC. 13 T. 32S R. 38 (XXXX/West)

SE - NW - SW SPOT LOCATION/QQQQ COUNTY STEVENS

1390 FEET (in exact footage) FROM S/x (circle one) LINE OF SECTION (NOT Lease Line)

1250 FEET (in exact footage) FROM x/W (circle one) LINE OF SECTION (NOT Lease Line)

163,662-C

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# (C-24,193)

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 605' CEMENTED WITH 390 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 2918' CEMENTED WITH 245 SACKS

2560-78, 2590-2620, 2632-69, 2708-38, 2751-82,

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: 2810-20, 2842-48, 2853-64.

ELEVATION 3155' / -- T.D. 2920' PBDT 2905' ANHYDRITE DEPTH 1704'-1778'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE  1-14-97

PROPOSED METHOD OF PLUGGING NOTIFY KCC DISTRICT OFFICE 72 HRS PRIOR TO PLUGGING: MIRU WL. RIH W/ CIBP & SET @ 2530'. DMP 2 SXS CMT ON CIBP. PMP 2575 GAL MUD TO LOAD-HOLE. RIH W/ 2-1/8" PERFORATING GUN & PERF 630'-631' W/ASPF. PMP MUD & ESTABLISH CIRC THRU CMT HOLES. PMP 122 SXS CMT & DISPLACE W/565 GAL MUD. PMP 6.5 SXS CMT FROM 53'-3'. CUT-OFF & CAP 8-5/8" & 5-1/2" CSG 3 FT BELOW GL. INSCRIBE CAP WITH WELL NAME & NUMBER. LEGAL DESCRIPTION, PLUG DATE, RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? (LOGS SUBMITTED WITH ORIGINAL ACO-1)

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MR. DAVE GILMORE PHONE# (316) 544-7240

ADDRESS P.O. BOX 208 City/State HUGOTON, KANSAS 67951

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151 1/98

(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1/7/97 AUTHORIZED OPERATOR/AGENT: John A. Broman

JOHN A. BROMAN (signature)  
DIVISION PRODUCTION ENGINEER

**ANADARKO PETROLEUM CORPORATION**

PHONE 316 - 624 - 6253    1701 NORTH KANSAS AVE.    P.O. BOX 351    LIBERAL, KANSAS 67905 - 0351



January 6, 1997

Kansas Corporation Commission  
Conservation Division  
Finney State Office Building  
130 South Market, Rm. 2078  
Wichita, Kansas 67202

Attn: Priscilla Zadoka

Re: Well Plugging Application Form (Form CP-1)

Beesley "D" No. 1H  
Section 13-32S-38W  
Stevens County, KS

RECEIVED  
KANSAS CORP COM  
1997 JAN 14 P 12:57

Dear Priscilla:

Enclosed in duplicate is a well plugging application (KCC Form CP-1) for the referenced well. Upon approval of this application, please notify this office at the letterhead address so that plugging operations may commence.

Very truly yours,

A handwritten signature in cursive script that reads "John A. Broman".

John A. Broman  
Division Production Engineer  
JMD/sh

Enclosure

cc: Well File  
Ken Lester - HGO  
Manager Land Administration - HGO  
WI Owners

kccintpa.doc



## Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner  
Judith McConnell, Executive Director David J. Heinemann, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 14, 1997

Anadarko Petroleum Corporation  
P O Box 351  
Liberal KS 67905-0351

Beesley "D" #1H  
API 15-189-21,281  
1390 FSL 1250 FWL  
Sec. 13-32S-38W  
Stevens County

Dear Mr. Dave Gilmore,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

  
David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760