

RECEIVED

MAY 28 2002
5-28-02
KCC WICHITA

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Finney State Office Building
130 South Market
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

A-2 M.

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-189-10010-000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS 701 S TAYLOR, SUITE 400 CITY AMARILLO

STATE TEXAS ZIP CODE 79101 CONTACT PHONE # (806) 457-4600

LEASE McClure "A" WELL# 2-16 SEC. 16 T. 32S R. 38 (XXXX/West)

C - NW - SE - XX SPOT LOCATION/QQQQ COUNTY STEVENS

1980 FEET (in exact footage) FROM N/X (circle one) LINE OF SECTION (NOT LeaseLine)

1980 FEET (in exact footage) FROM X/W (circle one) LINE OF SECTION (NOT LeaseLine)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# D-19-627

CONDUCTOR CASING SIZE 13" SET AT 586' CEMENTED WITH 575 SACKS

SURFACE CASING SIZE 8 5/8" SET AT 3047' CEMENTED WITH 850 SACKS

PRODUCTION CASING SIZE SET AT CEMENTED WITH SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 1500'-1600' (OA).

ELEVATION 3190 - T.D. 6085 PBDT 2760' ANHYDRITE DEPTH NA
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE
PROPOSED METHOD OF PLUGGING NOTIFY DISTRICT OFFICE 5 DAYS PRIOR TO PLUGGING. MIRU
PLUGGERS. MIX AND PUMP 5 SKS HULLS AND 70 SKS CLASS H CMT W/6% GEL FROM 1650' TO
1450'. DISPLACE CMT W/9 PPG MUD. TOH TO 34'. MIX AND SPOT 10 SKS CLASS H CMT FROM 34'
TO 4'. TOH. CUT OFF AND CAP 8 5/8" CSG 4' BELOW GL. INSCRIBE WELL NAME, NUMBER, LEGAL
DESCRIPTION, AND PLUGGING DATE ON CAP. RDMO PLUGGERS. RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? FILED WITH ORIGINAL ACO-1

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

DAWN NEASE PHONE# (620) 544-4344

ADDRESS PO BOX 40 City/State HUGOTON, KANSAS 67951

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 05/22/02 AUTHORIZED OPERATOR/AGENT: John M Vigil

JOHN VIGIL (Signature)
DIVISION DRILLING ENGINEER



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Anadarko Petroleum Corporation
17001 Northchase Drive
Houston, TX 77060

June 24, 2002

Re: MCCLURE #2-16
API 15-189-10010-00-01
CNWSE 16-32S-38W, 1980 FNL 1980 FWL
STEVENS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district, office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely


David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888