

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Finney State Office Building
130 South Market
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-189-20200-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549 8/98
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE Charity "A" WELL# 1 SEC. 19 T. 32S R. 37 (XXXX West)

- - C - NW SPOT LOCATION/QQQQ COUNTY STEVENS

1320 FEET (in exact footage) FROM N/X (circle one) LINE OF SECTION (NOT LeaseLine)

1320 FEET (in exact footage) FROM X/W (circle one) LINE OF SECTION (NOT LeaseLine)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 596 CEMENTED WITH 450 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 3007 CEMENTED WITH 650 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 2895-2994 (OA), Cmt' retainer @ 2854

ELEVATION 3162 - T.D. 3007 PBDT 2954 ANHYDRITE DEPTH NA
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____
PROPOSED METHOD OF PLUGGING NOTIFY DISTRICT OFFICE 5 DAYS PRIOR TO PLUGGING. MIRU CASING PULLERS. MIX AND PUMP 2 SKS HULLS AND 35 SKS CLASS H CMT FROM 2946' TO 2845'. DISPLACE CMT W/9 PPG MUD. DETERMINE FREE POINT. SHOOT OFF 5 1/2" CASING. TOH W/ CSG TO 696'. MIX & SPOT 65 SKS CLASS H CMT 696' TO 496'. TOH W/CSG TO 45'. MIX AND SPOT 15 SKS CLASS H CMT FROM 45' TO SURFACE. TOH W/REMAINING CSG. CUT OFF AND CAP 8 5/8" CSG 3' BELOW GL. RDMO CASING PULLERS. INSCRIBE WELL NAME, NUMBER, LEGAL DESCRIPTION, AND PLUGGING DATE ON CAP. RDMO CASING PULLERS. RESTORE LOCATION.

(If additional space is needed attach separate page)
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? FILED WITH ORIGINAL ACO-1

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

DAVID GILMORE PHONE# (316) 544-7240

ADDRESS P.O. BOX 208 City/State HUGOTON, KANSAS 67951

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151 1/99
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 4/20/98 AUTHORIZED OPERATOR/AGENT: Shawn Young
SHAWN YOUNG (signature)
DIVISION PRODUCTION ENGINEER



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Susan M. Seltsam, Commissioner Cynthia L. Claus, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

June 17, 1998

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Charity "A" #1
API 15-189-20,200
1320 FNL 1320 FWL
Sec. 19-32S-37W
Stevens County

Dear David Gilmore,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,
A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760