

RECEIVED
KANSAS CORP COMM

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

1997 SEP 18 P 12:21

FORM CP-1 (3/92)

9-18-97

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

API # 15-129-20841 - 0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Hugoton Energy Corporation KCC LICENSE # 3871 8/97
(owner/company name) (operator's)

ADDRESS: 301 N. Main St, Suite 1900 CITY: Wichita

STATE: KS ZIP CODE: 67202 CONTACT PHONE # (316) 262-1522

LEASE: Kirkpatrick A WELL # 1-21 SEC 21 T 32 R 42 West

CE/2 - SW - SW - SPOT LOCATION/QQQQ COUNTY Morton

660 FEET (in exact footage) FROM S (circle one) LINE OF SECTION (NOT Lease Line)

990 FEET (in exact footage) FROM W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET # _____

| | | | | | | |
|------------------------|--------------|--------|-------------|---------------|------------|-------|
| CONDUCTOR CASING SIZE | _____ | SET AT | _____ | CEMENTED WITH | _____ | SACKS |
| SURFACE CASING SIZE | <u>8-5/8</u> | SET AT | <u>1594</u> | CEMENTED WITH | <u>500</u> | SACKS |
| PRODUCTION CASING SIZE | <u>4-1/2</u> | SET AT | <u>5230</u> | CEMENTED WITH | <u>350</u> | SACKS |

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4947-4956

ELEVATION 3531 KB T.D. 5400 PBDT 5200 ANHYDRITE DEPTH 1570
(G.L./K.B) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Push plug to 4900'. Dump 25 sx cement, pump 5 sx hulls, 50 sx cement to 1450', Gelled spacer. 50 sx top plug. Check 8-5/8" to 500#. Pump 50 sx if needed, use 65/35 Poz w/ 6% gel

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? **YES/NO** IS ACO-1 FILED? **YES**

If not, explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Joe Brougher PHONE# (316) 287-3811

ADDRESS 4532 W. Jones Ave CITY/STATE Garden City, KS 67846

PLUGGING CONTRACTOR Hugoton Energy Corporation KCC LICENSE # 3871 8/97
(company name) (contractor's)

ADDRESS 301 N. Main, Suite 1900, Wichita, KS 67202 PHONE # (316) 262-1522

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9/16/97 AUTHORIZED OPERATOR/AGENT: _____

Earl Ringeisen
(signature) Earl Ringeisen



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

September 18, 1997

Hugoton Energy Corporation
301 N Main Suite 1900
Wichita KS 67202

Kirkpatrick A #1-21
API 15-129-20,841
660 FSL 990 FWL
Sec. 21-32S-42W
Morton County

Dear Joe Brougher,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760