

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-189-20567-W ⁻⁰⁰⁰¹ (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549 ^{8/97}
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE (316) 624-6253

LEASE NORDLING "A" WELL# 1H SEC. 23 T. 32S R. 38 (xxxx/West)

- C - W/2 - SE SPOT LOCATION/QQQQ COUNTY STEVENS

1320 FEET (in exact footage) FROM (S)x (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM (E)x (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8" SET AT 1768' CEMENTED WITH 850 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 2925' CEMENTED WITH 260 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: 2565-76, 2596-2630, 2654-76, 2706-50, 2762-96

ELEVATION 3180' / -- T.D. 2959' PBD 2924' ANHYDRITE DEPTH 1786' (BASE)
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING NOTIFY KCC DISTRICT OFFICE 72 HRS PRIOR TO PLUGGING. MIRU CSG PULLERS. SET CIBP @ 2550'. SPOT 7 SKS CLASS H CMT FROM 2550'-2496'. DISPLACE W/695 GAL 9PPG MUD. SPOT 13 SKS CLASS H CMT FROM 1818'-1718'. DISPLACE W/1706 GAL 9PPG MUD. SPOT 6.5 CLASS H CMT FROM 53'-3'. CUT-OFF & CAP 8-5/8" & 5-1/2" CSG STRINGS 3' BELOW G.L. & INSCRIBE CAP W/ WELL NAME & NO., LEGAL DESCRIPTION, & PLUGGING DATE. RDMO CSG PULLERS. RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? (LOGS SUBMITTED WITH ORIGINAL ACO-1)

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MR. DAVE GILMORE PHONE# (316) 544-7240

ADDRESS P.O. BOX 208 City/State HUGOTON, KANSAS 67951

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9-23-96 AUTHORIZED OPERATOR/AGENT: J.L. Ashpon

J.L. ASHPON (signature) DIV. PROD. MGR.

RECEIVED
KANSAS STATE CORPORATION COMMISSION
1996 OCT - 2 11:39 AM
10-2-96

JAMES L. ASHTON
DIVISION PRODUCTION MANAGER



September 23, 1996

Kansas Corporation Commission
Conservation Division
Finney State Office Building
130 South Market, Rm. 2078
Wichita, Kansas 67202

Attn: Priscilla Zadoka

Re: Well Plugging Application Form (Form CP-1)

Nordling "A" No. 1H
Section 23-32S-38W
Stevens County, KS

Dear Ms. Zadoka:

Enclosed in duplicate is a well plugging application (KCC Form CP-1) submitted for your approval to plug and abandon the referenced well. Upon approval of this application, please notify this office at the letterhead address so that plugging operations may commence.

Very truly yours,

A handwritten signature in black ink, appearing to read "J. L. Ashton", written in a cursive style.

J. L. Ashton
Division Production Manager
JMD/sh

Enclosure

cc: Well File
Ken Lester - HGO
Manager Land Administration - HGO
WI Owners

kccintpa.doc

RECEIVED
KANSAS CORP COMM
1996 OCT - 2 A 12: 39



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

October 3, 1996

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Nordling "A" #1H
API 15-189-20,567
1320 FSL 1980 FEL
Sec. 23-32S-38W
Stevens County

Dear Mr. Dave Gilmore,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760