

RECEIVED
STATE CORPORATION COMMISSION

FORM CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

SEP - 9 1980
9-9-80
CONSERVATION DIVISION
Wichita, Kansas

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County, Sec. 26 Twp. 29 Rge. 6W E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
NE SW SE

Lease Owner National Oil Co.
Lease Name Tonn #1 Well No. _____
Office Address Denver, Colorado
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 8/25/80 _____ 19____
Plugging completed 8/29/80 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4518
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	315	none
				4 1/2"	4287	3323'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Pumped 1 sack hulls, 35 sacks cement. Pumped plug to 3460'. Shot pipe at
3455', 3395', 3300', pulled 107 joints. Squeezed hole with 15 sacks gel,
8 sacks hulls, 10 sacks gel. Released plug and displaced with 125 sacks
50-50 pozmix, 4% gel and 3% cc.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of Sept., 19 80

My commission expires



Margaret Melcher
Notary Public.

15-095-20662-0000

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLING BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY National Oil Company

SEC. 26 T. 29S R. 6W
 LOC. C-NE SW SE


FARM Tonn

NO. 1

COUNTY Kingman

TOTAL DEPTH 4,518'
 COMM. January 18, 1978
 SHOT OR TREATED
 CONTRACTOR H-30, Inc.
 ISSUED February 13, 1978

COMP. February 2, 1978



CASING		
20	10	
15	8-5/8"	315' cemented w/350 sxs cement ELEVATION 1,534' K.B.
12	6	
13	5	
	4-1/2"	4,287' cemented w/150 sxs cement

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed and Shale	318'
Shale and Red Bed	572'
Shale	935'
Shale and Lime	1,305'
Lime and Shale	4,150'
Lime	4,165'
Lime and Shale	4,471'
Shale and Lime	4,512'
Sand	4,518'
Rotary Total Depth	4,518'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting

 Dean Britting

State of Kansas }
 County of Sedgwick } ss:

Suscribed and Sworn to before me a Notary Public in and for said county and state this 13th day of February, 1978.



Elsie Willison

 Elsie Willison - Notary Public

My Commission Expires:
 June 30, 1978

JUN 30 1980
 6-30-80