


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County. Sec. 26 Twp. 29 Rge. (E) 6 (W)
Location as "NE/CNW/SW" or footage from lines. C NW NW
Lease Owner Pickrell Drilling Company
Lease Name Ravenstein "A" Well No. 1
Office Address 705 4th Natl Bank Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 1, 1964
Application for plugging filed November 21, 1964
Application for plugging approved November 1, 1964
Plugging commenced November 1, 1964
Plugging completed November 1, 1964
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4561 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	200	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 240'. Set plug. Cemented with
25 sacks cement. Heavy mud to 40'. Set plug.
Cemented with 10 sacks cement bottom of cellar.
Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 13 1964
11-13-64
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PICKRELL DRILLING COMPANY
Address 705 Fourth National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebitts (employee or owner) of (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) C. W. Sebitts
705 4th Nat'l Bank Bldg, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 19 64
Maxine Blackman
Maxine Blackman, Notary Public.
My commission expires June 21, 1966

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th Nat'l Bank Bldg
Wichita, Kansas

Rotary Drilling Commenced 10-20-64

Rotary Drilling Completed 11-1-64

LOCATION: RAVENSTEIN "A" No. 1, C NW NW Section 26-29-6W, Kingman County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (10 jts) 8 5/8" surface casing set at 200', cemented with 155 sacks cement. Circulated. Completed 9:00 P.M. October 20, 1964. No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

35	Sand	
200	Red Rock	
650	Shale & Shells	<u>C. F. S.</u> 3275
1260	Shale, Shells & Lime	3290
3050	Lime & Shale	3295
3245	Lime, Shale & Sand	3560
3310	Sand & Lime	3570
3587	Lime & Shale	3587
3810	Lime	3610
4124	Lime & Shale	3706
4395	Mississippi	3744
4435	Mississippi & Kinderhook	4106
4481	Kinderhook	4135
4493	Kinderhook & Cherty Lime	4150
4501	Shale (Kinderhook)	4481
4537	Viola	4486
4543	Simpson Sand	4493
4561	Sand & RTD	4505
		4511
		4523
		4534

Slope Test
2500
3000
3500
4000

S. L. M.
3675
4000
4300

RECEIVED
STATE CORPORATION COMMISSION
NOV 13 1964
11-13-64
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 9th day of November, 19 64, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public