


STATE OF KANSAS  
STATE CORPORATION COMMISSION

All Information Completely  
Made Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Harper County. Sec. 9 Twp. 35S Rge. (E) 5 (W)

Location as "NE/CNW&SW" or footage from lines NW NW SE  
Lease Owner Russell Cobb, Jr., Inc.  
Lease Name C. D. Williams Well No. 1  
Office Address Thompson Building, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 16, 1955 19  
Application for plugging filed June 16, 1955 (verbal) 19  
Application for plugging approved June 16, 1955 (verbal) 19  
Plugging commenced June 16, 1955 19  
Plugging completed June 16, 1955 19  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 148, Pratt, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 5212 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	260	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used  
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Filled hole to 240' with  
mud and hulls. Bottom  
plug set at 240' with 20  
sacks cement through pipe.  
Top plug set at 35' with  
1/4 sack hulls and 10 sacks  
cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graham-Messman-Rinehart Drilling Company (License No. 20)  
Address 1005 East Second, Wichita, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.  
L. E. Wilsey (employee of owner) or (Conservation Agent) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. E. Wilsey*  
811 Thompson Building - Tulsa, Oklahoma  
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of June, 19 55

My commission expires January 11, 1959.

*Janice M. Matheson*  
Notary Public  
STATE CORPORATION COMMISSION

**PLUGGING**  
FILE SEC 9 T 35 R 5W  
BOOK PAGE 422 LINE 3

JUN 30 1955  
CONSERVATION DIVISION  
Wichita, Kansas

6-30-55

NO. 1 C. D. WILLIAMS

WELL RECORD

Location: NW NW SE, 9-35S-5W  
Harper County, Kansas

Operator: Russell Cobb, Jr., Inc.  
Thompson Building, Tulsa, Oklahoma

Contractor: Graham-Messman-Rinehart Drilling Co.  
1005 East Second, Wichita, Kansas

Casing Record: 8 5/8" at 260' w/175 sacks cement

Commenced: May 28, 1955  
Completed: June 16, 1955  
Elevation: 1233 R.B.  
Production: Dry

.....L O G.....

Red Bed	264
Red Bed-Shells	500
Shale	910
Shale-Lime	1316
Shale-Sandy Lime	1514
Shale	1520
Lime-Shale	1647
Shale-Lime	1891
Lime-Shale	2818
Shale-Lime	3228
Lime-Shale	3555
Sand-Shale	3730
Lime-Shale	3838
Shale-Lime	3912
Lime-Shale	4019
Lime	4430
Shale	4584
Shale-Lime	4616
Miss. Lime	4723
Lime	4737
Lime-Chert	4740
Lime	4789
Chert	4804
Lime-Chert	4912
Chert-Lime	4946
Lime	5060
Lime-Shale	5131
Shale	5194
Shale-Sand	5212 R.T.D.

Sample Tops:

Kansas City 3904 (-2671)  
Mississippi 4610 (-3377)  
Base Miss. 5095 (-3862)  
Viola 5090 (-3957)  
Simpson Sand 5204 (-3971)

The undersigned, GRAHAM-MESSMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART DRILLING COMPANY

By: J. A. Gilliland  
J. A. Gilliland

Subscribed and sworn to before me this 20th day of June 1955.

Juanita L. Louis  
Notary Public

My Commission Expires: November 5, 1958

**PLUGGING**  
FILE NO. 9-35-5W  
BOOK PAGE 127 LINE 3

6-30-55  
**RECEIVED**  
STATE CORPORATION COMMISSION  
JUN 30 1955  
CONSERVATION DIVISION  
WICHITA, KANSAS