


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
312 North Market, Insurance Bldg.
Wichita, Kansas

Sumner County. Sec. 9 Twp. 35 Rge. XXX 4 (W)
Location as "NE/CNW%SW%" or footage from lines SW NW NW
Lease Owner Pentagon Corporation
Lease Name Kolarik Well No. 1
Office Address 515 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed June 24, 19 61
Application for plugging filed June 24 19 61
Application for plugging approved June 24 19 61
Plugging commenced June 24 19 61
Plugging completed June 24 19 61
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lee Guthrie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5039 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
NONE						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud @ 180 feet
Wooden plug @ 180' with 1/4 sack hulls and 15 sacks cement on top of plug.
Mud 35 feet.
Wooden plug 35 feet with 1/4 sack hulls, 2 sacks cement and 10 sacks cement on top of plug
2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1961 6-27-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Fortune Oil & Gas, Inc.
Address 918 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Robert L. Jones (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
918 Central Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of June 19 61
Jane E. Chick
Notary Public.
My commission expires September 24, 1962

15-191-00147-0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

R


COMPANY *Pentagon Corporation*

SEC. 9 T. 35S R. 4W
LOC. SW NW NW

FARM *Kolarik* NO. 1

TOTAL DEPTH *5039*
COMM. *6-1-61* COMP. *6-24-61*
SHOT OR TREATED
CONTRACTOR *Fortune Oil and Gas, Inc.*
ISSUED

COUNTY *Sumner*
KANSAS



CASING

20 10
15 8 *5/8" surface casing @223' with 200 sacks* ELEVATION *1177 K.B.*
12 6 *of Portland, 15 sacks of Gel, 15 sacks of*
13 5 *salt Gel and 12 sacks of hulls.* PRODUCTION *D & A*

FIGURES INDICATE BOTTOM OF FORMATIONS

0	1085	Shale and Lime
1085	1208	Shale
1208	2150	Shale and Lime
2150	2310	Shale
2310	2340	Shale and Lime
2340	2656	Shale
2656	3458	Shale and Lime
3458	3630	Sand and Shale
3630	3780	Shale and Lime
3780	3848	Sand and Shale
3848	3870	Shale
3870	3996	Lime
3996	4068	Shale and Lime
4068	4170	Lime
4170	4400	Shale and Lime
4400	4484	Shale
4484	4601	Lime and Shale
4601	5002	Lime
5002	5025	Shale
5025	5039	Sand and Dolomite
	5039	Total Depth - D and A.

I do hereby certify that the above and foregoing is a true and correct copy of the log of the Kolarik #1, located in the SW NW NW of Sec. 9-T 35 S - R. 4 W, Sumner County, Kansas, as reflected by the files of Fortune Oil, & Gas, Inc.

PENTAGON CORPORATION

Howard A. Stoskopf
Howard A. Stoskopf

State of Kansas)
)ss:
Sedgwick County)

Subscribed and sworn to before me, a Notary Public, in and for the County of Sedgwick, State of Kansas, this _____ day of June, 1961.

My commission expires:

May 31, 1965

Dorothy J. Kimball
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1961 7-12-61

CONSERVATION DIVISION
Wichita, Kansas