

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-191-22,092-0000

LEASE NAME Nulik

WELL NUMBER 5-1

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 5 TWP. 35 RGE. 4 X(E) or (W)

COUNTY Sumner

Date Well Completed 1-08-89

Plugging Commenced 1-09-89

Plugging Completed 1-09-89

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Hazelwood Production & Exploration Co.

ADDRESS 6801 N. Broadway-Suite 320 Oklahoma City, OK 73116

PHONE#(405) 848-6884 OPERATORS LICENSE NO. 3734

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-08-89 (date)

by Steve Vangieson (KCC District Agent's Name).

Is ACO-1 filed? to be filed by operator If not, Is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom 5210

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS _____ CASING RECORDS _____

Formation	Content	From	To	Size	Put in	Pulled out

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 13 1989
 CONSERVATION DIVISION
 WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
 Bottom Plug: @5140' w/35 sacks cement thru drill pipe

Next Plug: @1100' w/25 sacks " " " " Top Plug: @60' w/25 sacks cement
 Next Plug: @670' w/25 " " " " 10 sacks in Rat Hole
 Next Plug: @320' w/35 " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hazelwood Production & Exploration Co.

STATE OF Kansas COUNTY OF Barton, ss.

John Armbruster (Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) John Armbruster

(Address) P.O. Box 823 Great Bend, KS 67530



AND SWORN TO before me this 12 day of January, 19 89

Dorothy M. Hague
 Notary Public

My Commission Expires: _____

DRILLER'S WELL LOG

DATE COMMENCED: December 23, 1988
DATE COMPLETED: January 9, 1989

Hazelwood Production & Expl.
C SE NE
SEC. 5, T35S, R4W
"Nulik #5-1"
Sumner County, Ks.

0	-	272'	Surface Soil, Sand
272	-	1005'	Red Bed, Shale
1005	-	2425'	Shale & Lime
2425	-	2652'	Shale
2652	-	3291'	Lime & Shale
3291	-	4267'	Lime
4267	-	4531'	Lime, Shale, Chert
4531	-	4858'	Chert & Lime
4858	-	4982'	Shale
4982	-	5151'	Sand
5151	-	5210'	Dolomite
		5210'	RTD

ELEVATION: 1202' K.B.

Surface Pipe: Set new
8-5/8", 20# pipe @272'
w/200 sacks 60/40 pozmix
2% gel 3% cc

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1989
CONSERVATION DIVISION
Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS,
COUNTY OF BARTON) ss

John Armbruster of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

John J. Armbruster

Subscribed and sworn to before me this 12 day of January 1989.

Dorothy M. Hague
Notary Public

