

15-191-21128-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
205 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-00177852

LEASE NAME Williams

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~
W/2 NE SW
~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~

LEASE OPERATOR Ceja Corporation

SEC. 16 TWP. 35S RGE. 3 ~~XXXX~~ (W)

ADDRESS 6120 S. Yale, Suite 1800, Tulsa, OK 74136

COUNTY Sumner

PHONE#(918 496-0770) OPERATORS LICENSE NO. 8465

Date Well Completed _____

Character of Well Oil

Plugging Commenced 12/16/97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1/07/98

The plugging proposal was approved on November 17, 1997 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, Is well log attached? N/A

Producing Formation Simpson Depth to Top 4829 Bottom 4847 T.D. 5208

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Simpson	Oil & Gas	4829	4847	5 1/2	thru	None
Miss Chat	Oil & Gas	4396	4416	5 1/2	thru	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Displaced well bore fluids with mud thru 2 3/8 tbg. Pumped class A cmt. plugs thru 2 3/8" tbg. as follows: 20 sacks from 4847' to 4698', 20 sacks from 4416' to 4267', 50 sacks from 3145' to 2997', 20 sacks from 700 to 652 and 135 sacks from 200' to surface. Well has retrieve D Pkr. 0 4900

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Ceja Corporation License No. 8465

Address 6120 S. Yale, Suite 1800, Tulsa, OK 74136

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ceja Corporation

STATE OF Oklahoma COUNTY OF Tulsa, ss. Wichita, Kansas

Sherrie Garcia (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Sherrie Garcia

(Address) 6120 S. Yale, Suite 1800, Tulsa, Oklahoma 74136

SUBSCRIBED AND SWORN TO before me this 10th day of February, 1998

Frank C. Saluberry
Notary Public

My Commission Expires: March 21, 2001