


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Sumner County, Sec. 16 Twp. 35S Rge. 3 ~~NE~~W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines 480' FNL & 480' FEL NW SW NE NE NW

Lease Owner Herndon Drilling Company  
Lease Name Williams 'B' Well No. 1  
Office Address 324 S. Main, Tulsa, Okla. 74101  
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole



Locate well correctly on above Section Plat

Date Well completed 11-11 19 78  
Application for plugging filed 11-11 19 78  
Application for plugging approved 11-11 19 78  
Plugging commenced 11-11 19 78  
Plugging completed 11-11 19 78

Reason for abandonment of well or producing formation no commercial quantities of oil or gas encountered  
If a producing well is abandoned, date of last production. 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Carl Barnett  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4900  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION    | CONTENT | FROM | TO   | SIZE   | PUT IN | PULLED OUT |
|--------------|---------|------|------|--------|--------|------------|
| surface hole | shale   | surf | 242' | 8-5/8" | 240'   | none       |
|              |         |      |      |        |        |            |
|              |         |      |      |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fluid to 225', plug, 25 sx  
Fluid to 40', plug, 15 sx  
3 sx in rat hole

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 17 1978  
11-17-78  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_

STATE OF Kansas COUNTY OF Sedgwick, ss. \_\_\_\_\_  
(employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gilla Press  
515 R.H. Garvey Bldg., Wichita, Ks., 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of November, 19 78

My commission expires April 30, 1979

Dorothy L. Schmidt  
Dorothy L. Schmidt Notary Public.

DOROTHY L. SCHMIDT  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Appt. Exp. April 30, 1979

DRILLER'S LOG

HERNDON DRILLING COMPANY  
No. 1 Williams 'B'  
480' FNL & 480' FEL  
NW/4 SW/4 NE/4 NE/4 NW/4  
Sec. 16-35S-3W  
Sumner Co., Ks.

Surface Casing: 240' of 8-5/8"  
cmtd w/175 sx cmt, 3% cc.  
10/28/78

Commenced: 10-28-78  
Completed: 11-11-78

| <u>FORMATION</u>   | <u>DEPTH</u>    |
|--------------------|-----------------|
| Surface Hole       | 0 - 242         |
| Shale              | 242 - 629       |
| Shale & Lime       | 629 - 961       |
| Lime & Shale       | 861 - 1710      |
| Sand & Shale       | 1710 - 1814     |
| Shale, Lime & Sand | 1814 - 1922     |
| Shale & Lime       | 1922 - 2096     |
| Lime               | 2096 - 2125     |
| Shale              | 2125 - 2235     |
| Shale & Lime       | 2235 - 2486     |
| Lime               | 2486 - 2625     |
| Lime & Shale       | 2625 - 2875     |
| Shale & Lime       | 2875 - 2826     |
| Shale              | 2826 - 2935     |
| Lime & Shale       | 2935 - 2958     |
| Shale & Lime       | 2958 - 3282     |
| Shale & Sand       | 3282 - 3343     |
| Shale & Lime       | 3343 - 3727     |
| Lime               | 3727 - 3755     |
| Lime & Shale       | 3755 - 3827     |
| Shale & Lime       | 3827 - 3988     |
| Lime               | 3988 - 3995     |
| Lime & Shale       | 3995 - 4210     |
| Shale & Lime       | 4210 - 4328     |
| Lime & Shale       | 4328 - 4397     |
| Shale              | 4397 - 4420     |
| Lime               | 4420 - 4825     |
| Shale              | 4825 - 4886     |
| Simpson Sand       | 4886 - 4900 RTD |

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 17 1978  
11-17-78  
CONSERVATION DIVISION  
Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.  
*Ella Dress*  
Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 14th day of November, 1978.

DOROTHY L. SCHMIDT  
STATE NOTARY PUBLIC  
Sec. 16-35S-3W, Kansas  
My Appt. Expires 30-1979

*Dorothy L. Schmidt*  
Dorothy L. Schmidt, Notary Public