

15-095-00445-0000


STATE OF KANSAS
STOCK CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD Strike out upper line when reporting plugging of formations.

Kingman County, Sec. 25 Twp. 29 Rge. 10 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW NW/SW
Lease Owner Herndon and Herndon
Lease Name Gilbert Well No. 1
Office Address Box 489, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed December 24 1949
Application for plugging filed January 2 1950
Application for plugging approved January 3 1950
Plugging commenced January 3 1950
Plugging completed January 3 1950
Reason for abandonment of well or producing formation dry hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Rural Durkey
Producing formation Depth to top Bottom Total Depth of Well 4735 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4	518'	None
				16'	150	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with good mud to 275. Bridged hole set Halliburton plug @ 275. Put 20 sacks of cement on plug with Halliburton. Filled hole with mud to 10 ft. below ground Bridged hole. Set Halliburton plug. Filled with cement to ground level.

RECEIVED
JAN 10 1950 1-10-50

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Herndon and Herndon
Address Drawer 489, Tulsa, Oklahoma

STATE OF Oklahoma COUNTY OF Tulsa, SS.

W. G. Prather (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. G. Prather
Box 436, Lyons, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 9th day of January, 19 50

My commission expires Sept. 19, 1952

J. L. [Signature] Notary Public.

PLUGGING
FILE SEC 25 T 29 R 10 S
BOOK PAGE 132 LINE 24

15-095-00445-0000

WELL LOG ON GILBERT #1

Spudding date: 11-30-49

Date casing set: Dry

Location:

Date rotary completed: 12-24-49

NW NW SW Sec. 25-29S-10W, Kingman County
Kansas

Date cable completed:

FROM	TO	FORMATION	REMARKS
0	50	Surface Hole	Ran 3 Jts. 16" O.D. Used Csg.
50	475	Red bed	Total Csg. run 59'65" pipe set @ 50' R.B.
475	790	Shale	Cemented W/ 100 Sks & 300# C.C.
790	1120	Shale and shells	Layed down 5" drill pipe, ran 13 Jts. 10 3/4"
1120	1160	Salt	Spiral-Weld Csg., Total Csg. run 520', Pipe
1160	1420	Shale and shells	Set @ 518', Cemented W/ 400 Sks Bulk & 400#
1420	1470	Lime	C.C.
1470	1570	Lime and shale	
1570	2220	Lime	
2220	2965	Lime and shale	
2965	3105	Lime	
3105	3570	Lime	
3570	3645	Lime and shale	
3645	4237	Lime	
4237	4270	Chert and lime	
4270	4300	Chert and lime	
4300	4323	Lime and shale	
4323	4350	Shale and lime	
4350	4395	Lime and shale	
4395	4520	Shale	
4520	4685	Lime and shale	
4685	4695	Shale	
4695	4735	Lime - T. D.	Dry

PLUGGING
 FILE SEC 25 T 29 R 10 W
 BOOK PAGE 137 LINE 26

RECORDED
 1-26-50
 JAN 26 1950
 STATE OF KANSAS
 COMMISSIONER
 KANSAS

Subscribed and sworn to before me this 9th
 day of January 19 50

I certify the above and foregoing to be a true and exact
 copy of the original driller's log on the Gilbert #1

Clare Steger
 Notary Public
 My commission expires:
 My commission expires Aug. 28, 1951

HERNDON DRILLING COMPANY
[Signature]
 By
 Title: