

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 18 Twp. 30S Rge. 7 (E) (W) X

Location as "NE/CNW&SW" or footage from lines NE SE NW

Lease Owner Mull Drilling Company, Inc.

Lease Name Towner-Wells Well No. 1

Office Address 1625 Wichita Plaza Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 6-16-67 19

Application for plugging approved 6-17-67 19


Plugging commenced 7-6-67 19

Plugging completed 7-9-67 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie V. Elving

Producing formation Depth to top Bottom Total Depth of Well 1164 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	222	None
				4 1/2	None	2111

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Cleaned out cellar.

Sanded to 4100'. Dumped 4 sacks of cement. Worked pipe. Shot pipe at 2400' - 2300' - 2200' and 2100'.

Pulling pipe. Plugging well. Set rock bridge at 220'. Dumped 25 sacks of cement. Filled hole and rock bridge. Capped well with 10 sacks of cement.

Cleaned and doped collar threads.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 12 1967  
7-12-67  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes

P. O. Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 10 day of July, 19 67

My commission expires May 27, 1969

Notary Public.

ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Et Al  
Wichita, Kansas

ROTARY DRILLING COMMENCED: 11/26/60

CONTRACTOR: Mull Drilling Co., Inc.  
Wichita, Kansas

ROTARY DRILLING COMPLETED: 12/13/60

CASING RECORD: Set 8 5/8" @ 222' w/160 sx cmt.  
Set 4 1/2" @ 4164' w/125 sx cmt.

LOCATION: TOWNER-WELLS #1  
NE SE NW 18-30S-7W  
Kingman County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing.)

650'	Red Bed
1100'	Shale w/Shells
1370'	Shale w/Lime
1435'	Lime
1615'	Lime w/Shale
1770'	Lime
2850'	Lime & Shale
3442'	Sandy Lime & Shale
3709'	Lime w/Shale
3752'	Lime
4139'	Lime w/Shale
4184'	Mississippi Chert - total depth

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 19 1967  
6-19-67  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

*Robert G. Reinke*

Robert G. Reinke  
Geologist

STATE OF KANSAS )  
                          ) - SS  
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 19th day of December, 1960



*Madge N. Miller*  
Notary Public

My Commission Expires: February 24, 1960