


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Kingman County, Sec. 17 Twp. 30S Rge. 7W (E) (W)  
Location as "NE/CNW/SW" or footage from lines C SE NW  
Lease Owner Pickrell Drilling Company  
Lease Name Wells-Towner "C" Well No. 1  
Office Address 705 Fourth National Bank Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 18 19 73  
Application for plugging filed July 18 19 73  
Application for plugging approved July 18 19 73  
Plugging commenced July 18 19 73  
Plugging completed July 18 19 73  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production N/A 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4560 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom Plug @ 150' w/25 sacks,  
top plug @ 40' w/10 sacks

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 25 1973  
CONSERVATION DIVISION  
Wichita, Kansas  
7-25-73

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 Fourth National Bank Bldg., Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of July, 1973



My commission expires \_\_\_\_\_  
Helen L. Sage Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Building  
Wichita, Kansas 67202  
LOCATION: Wells-Towner "C" No. 1, C SE NW  
Section 17-30S-7W, Kingman County, Kansas

Rotary Drilling Commenced July 5, 1973  
Rotary Drilling Completed July 18, 1973

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: Run 5 Jts. 8 5/8" surface casing set at 200' K.B.  
with 150 sacks. Completed 8:00 P.M. Circulated.  
On oil string run. D & A.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 25 1973  
CONSERVATION DIVISION  
Wichita, Kansas  
7-25-73

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Sand		C.F.S.
200	Red Beds		3620
500	Shale & Red Beds		3670
1230	Shale		3765
1600	Shale & Lime Stringers		3797
2550	Lime & Shale		4175
2710	Shale & Lime Stringers		4490
2925	Lime & Shale		4503
3325	Shale & Lime		4510
3575	Lime		4525
3675	Shale & Lime		4537
3845	Lime		4545
3940	Lime & Shale		4553
4232	Lime		S.L.M.
4270	Lime, Shale, Chert	Board	3354.43
4330	Lime	Strap	3353.66
4560	Lime & Shale, RTD		<u>.77</u> Difference

Slope Tests

2000
2500
3000
3500
4000

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports;

PICKRELL DRILLING COMPANY  
By [Signature]  
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 23rd day of July, 1973, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.  
Given under my hand and seal of office the day and year last above written.

My commission expires: April 17, 1977

[Signature]  
Helen L. Sage Notary Public

